

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-21,867-00-00

SE. NW-SE, Sec. 34, T 8 S, R 21 W/E

1650 feet from N(S) section line

1650 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6984

Lease Name TALBERT Well # B-1

Operator: D. + A. OIL
Name & Address: BOX 94
DAMAR, MO.
67632

County GRAHAM

Well Total Depth 3705 feet \$120.41

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 257

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor PIONEER DRILLING License Number 146.256 5665

Address 308 WEST MILL, PLAINVILLE, MO. 67663

Company to plug at: Hour: 3:00 AM Day: 10th Month: OCT Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO TOM. ALM.

(company name) PIONEER DRILLING, INC. (phone) 913-839-9270

were: 8 5/8" - 257' EI S.P. CUL #150 SK 60/40 Pozmix. 2% GEL-3% CA-CL. (ALLIED)

ORDER 200 SK 50/150 Pozmix 6% GEL-3% CA-CL. AND 8 5/8" Plug

SPOT WITH DRILL STEM-TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.

AIRBUCKET @ 3690' EI

Signed [Signature] (TECHNICIAN) DOIC

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:00 AM Day: 10th Month: OCT Year: 1983

ACTUAL PLUGGING REPORT

ORDERED 200 SK 50/150 Pozmix 6% GEL-3% CA-CL. AND 8 5/8" Plug

SPOTTED WITH DRILL STEM-TURNED HOLE OVER, HEAVY MUD BETWEEN ALL PLUGS.

1st Plug @ 3660' EI #20 SK CNT., 2nd Plug @ 1620' EI #20 SK CNT.

3rd Plug @ 930' EI #100 SK CNT., 4th Plug @ 270' EI #40 SK CNT.

5th Plug ^{Solid Bridge} HULLS-Plug @ 40' EI #10 SK CNT. 10 SK IN RAT HOLE (CIRCULAR)

Remarks: CEMENTED BY ALLIED CNT.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED RECEIVED STATE CORPORATION COMMISSION

DATE 10-25-83 OCT 14 1983 10-14-83

Signed [Signature] (TECHNICIAN)

INV. NO. 5840-602 CONSERVATION DIVISION Wichita, Kansas