

6 031368

6-8

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-02040-00-01

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Operator: Oxy USA INC.

Name &

Address Box 26100

Oklahoma City, Ok. 73126-0100

SEC. 7, T 8 S, R 22 W/4E

4583 feet from S section line

375 feet from E section line

Lease Name Harmony S Well # 305 S

County Graham 53.14

Well Total Depth 1635 feet

Conductor Pipe: Size feet

Surface Casing: Size 4 1/2 feet 1635

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated Supply Well C.H.

Plugging Contractor Murfin Drilling Co. License Number 6033

Address Hill City, Ks.

Company to plug at: Hour: PM Day: 8 Month: June Year: 19 90

Plugging proposal received from Rick

(company name) Oxy USA (phone)

were: 4 1/2 set at 1635 . PBTB 1500'. Cement circ. from 1635 to surface.

Perf from 1435 to 1475. Completed as C.H. Supply Well.

Order work string and workover rig. Order 8 sks 65/35 poz 6% poz 200# hulls.

Allied Cement Co. Murfin Drilling Co. Rig OWS Water.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)Plugging Operations attended by Agent?: All ☒ Part None

Operations Completed: Hour: 1:15PM Day: 8 Month: June Year: 19 90

ACTUAL PLUGGING REPORT Ran tubing to 1460'. Mixed and pumped 40 sks cement

blend, mixed and pumped 40 sks cement blend w/200# hulls mixed in to max psi 1300#.

Close in psi 0 as hole was blown at 3' in 4 1/2". Plugging string was sanded in hole.

Backed off top two joints and squeezed 4 1/2 as above. Plug complete.

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-9-90

INV. NO. 28559

Signed

Carl Goodrow
(TECHNICIAN)