

12-22 15-065-00176-00 00

6 031208

API NUMBER 15- 1951

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE SE SE , SEC. 20 , T 8 S, R 22 W/E  
330 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5058

Lease Name Moore Well # 1

Operator: Griggs Oil Inc.  
Name & Address: 107 N. Market Suite 800  
Wichita, Ks. 67202

County Graham 126.59

Well Total Depth 3895 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Casing: Size 8 5/8 feet 137

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cement Co. License Number \_\_\_\_\_

Address Russell, Ks.

Company to plug at: Hour: AM Day: 22 Month: Dec Year: 19 88

Plugging proposal received from Wilber Berg

(company name) Griggs Oil (phone) \_\_\_\_\_

were: 8 5/8" set at 137' w/150 sks. 5 1/2" set at 3895' w/150 sks. PBSD 3806'.

Perfs 3616' - 3639'. Shots at 1730' anhy, and 1375' below Dakota. Order 300 sks

65/35 Poz 10% Gel 2% Dical 500# Hulls. Allied Cement Co. OWS Water Truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:45AM Day: 22 Month: Dec Year: 19 88

ACTUAL PLUGGING REPORT Squeeze 5 1/2" casing w/300 sks cement w/400# Hulls

mixed in with last 250 sks to max psi 600#. Close in psi 400#. Squeezed 8 5/8" annulus

w/100 sks 100 Hulls to max psi 300#. Close in psi 200#. Plug completed.

Remarks: (If additional description is necessary, use BACK of this form.)

I did ~~not~~ observe this plugging.

INVOICED

DATE 1-19-87

INV. NO. 23699

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow