

6 070235

API NUMBER 15-065-22, 082 00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW-SE-SW, SEC. 3, T. 8 S, R. 22 W

990 feet from S/E section line

3630 feet from S/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name JONES H.J. Well # 1

Operator: PETROLEUM, INC.

County GRAHAM

Name & Address 300 W. DOUGLAS, # 800

Well Total Depth 3810 123.83 feet

WICHITA, KANSAS.

Conductor Pipe: Size 0 feet

67202

Surface Casing: Size 8 5/8 feet 359

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D.N.B. DRILL, INC. License Number 5476

Address 535 N. OLIVER, WICHITA, KANSAS. 67208

Company to plug at: Hour: 1:00 PM Day: 15 Month: OCT. Year: 19 84

Plugging proposal received from JACK TAYLOR

(company name) DNB. DRILL, INC. (phone) 316-793-8471

were: 8 5/8" - 359' SP. CUC #1250 2% 3% Pozmix GEL - CH-CL - (BY HALLIBURTON)  
ORDER-220 1/50 Pozmix GEL - CH-CL - 1' CELE AND 8 5/8" PLUG

SPOT WITH DRILL STEM - TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.

NO CIRCULATION PROBLEMS, EIV. 2135 - ANH. 1761, ARBUCKLE @ 3759'

RECEIVED STATE CORPORATION COMMISSION

10-18-84

Plugging Proposal Received by Marion Smith (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X None \*

Operations Completed: Hour: 3:30 PM Day: 15th Month: OCT Year: 19 84

ACTUAL PLUGGING REPORT ORDERED 220 1/50 Pozmix GEL - CH-CL - 1' CELE + 8 5/8" PLUG

SPOTTED WITH DRILL STEM, MUD VISCOSITY 52 WEIGHT 9.6, MUD BETWEEN ALL PLUGS

1st Plug @ 3750 ET #1250 CNT. 2nd PLUG @ 1740 ET #1250 CNT.

3rd Plug @ 960 ET #100 + 1' CELE 4th PLUG @ 360 ET #50 CNT.

2nd Plug SOLID BRIDGE HULL'S-PLUG @ 40 ET #10 CNT. (CEMENTED BY HALLIBURTON)

Remarks: WITNESSED BY GILBERT BALTHAZOR (If additional description is necessary, use BACK of this form.)

I did (did not) observe this plugging.

DATE 10-29-84

Signed Marion Smith (TECHNICIAN) BOIK

INV. NO. 4517

NOV 19 1984

FORM CP-2/3 Rev. 01-84 10-17-84