

6030395

API NUMBER 15-065-21,084 <sup>00-00</sup> R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

CSESE, SEC. 4, T 8 S, R 22 W

660 feet from #S section line

660 feet from #E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5141

Lease Name Chalfant Well # 1

Operator: Zenith, Org. Corp.

County Graham 117.20

Name & Address 4th. Financial Ctr.

Well Total Depth 3606 feet

Ste. 505

Conductor Pipe: Size \_\_\_\_\_ feet

Wichita, Kansas 67202

Surface Casing: Size 8 5/8 feet 223

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Plugging License Number 6050

Address Chase Kansas

Company to plug at: Hour: PM Day: 14 Month: 3 Year: 19 85

Plugging proposal received from Millard Kelso.

(company name) Kelso Casing Pulling (phone) \_\_\_\_\_

were: 8 5/8 act @ 223' w/ 185 act 4 1/2 act @ 3605 w/ 100 act Perf. @ 3514-18'

3532-36' T.O.C. 3250' Ordered 170 act 50/50 pg 6 1/2 gel 3 1/2 cc 40 act gel

4 act hulls. applied cement. Recovered 3014' of 4 1/2" casing

RECEIVED STATE CORPORATION COMMISSION

MAR 28 1985 3-28-85

CONSERVATION DIVISION  
Plugging Proposal Received by Carl Goodnow (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X None \_\_\_\_\_

Operations Completed: Hour: 2:30 PM Day: 14 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT Bottom plug 4 act Com. Cem. Sand to 3450 - 4 act Com. Cem.

with Barite. Top plug pump down 8 5/8 - 4 act hulls - 25 act gel - 100 act

Cem. mix. - 15 act gel - Release 8 5/8 w. P. - 70 act Cem. Mix. Max Press = 500<sup>th</sup>

Shut in 200<sup>th</sup> Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

4-3-85  
7536

Signed Carl Goodnow (TECHNICIAN)

3-27-85  
15