

6 060155

17

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-21, 914-00-00

NW, SEC. 5, T. 8 S, R. 22 W1/4

1650 feet from N1/4 section line

990 feet from W1/4 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7107

Lease Name Bassett Well # 1

Operator: Dakota Resources, Inc.

County Graham

Name & Address 1700 Lincoln St.

Well Total Depth 3650 118.62 feet

Denver, Co. 80203

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 221' w/ 150 sh

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Co. License Number 158

Address Box 1389, Great Bend, Ks. 67530

Company to plug at: Hour: 4:30 PM Day: 11 Month: Feb. Year: 19 84

Plugging proposal received from Frank Allen

(company name) Allen Drilling Co. (phone) 316-793-5681

were: Order 180 sh. 90% foamix - 6% Gel. - 3% Col. Cl. 1 lb. Flo-Cell + 8 5/8" plug
Spot w/ drill pipe w/ no less than 30% mud between all plugs.

Elev. 2167

Andy, 1791

Allied Plugging Proposal Received by Gallo G. Gallo (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30 PM Day: 11 Month: Feb. Year: 19 84

ACTUAL PLUGGING REPORT

1st plug C 1800' w/ 20 sh.
2nd plug C 950' w/ 100 sh. & 1 lb. Flo-Cell
3rd plug C 275' w/ 40 sh.
4th plug - solid bridge of shells & plug C 40' w/ 10 sh. & 10 sh. in rat hole.
Good circulation & heavy mud between all plugs

Remarks: _____

INVOICED

(if additional description is necessary, use BACK of this form.)

I ~~did~~ / did not) observe this plugging.

DATE 3-8-84

Signed Gallo G. Gallo (TECHNICIAN)

INV NO. 0580

RECEIVED
STATE CORPORATION COMMISSION
MAR 05 1984
CONSERVATION DIVISION
Wichita, Kansas