

4-031832

6-24

-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-20,939

N2 NW NE /4 SEC. 20 , 08 S, 22 W  
4950 feet from S section line  
1980 feet from E section line

Operator license# 3738 Lease Quint well # 1

Operator: Sunrise Oilfield Supply, Co. County Graham

Address: N. Highway 283 Well total depth 3840 feet <sup>124.80</sup>  
P.O. Box 8 Conductor Pipe: 0 inch @ 0 feet  
Ness City, Kansas 67560 Surface pipe 8 5/8 Inch @ 262 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 24 Month: June Year: 93

Plugging proposal received from: Mike

Company: Sunrise Oilfield Supply, Co. Phone: \_\_\_\_\_

Were: Order 200 sx. 65/35 pozmix - 10% gel. - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 12:15P.M., Day: 24, Month: June, Year: 93

Actual plugging report: 8 5/8" set @ 262' w/180 sx. 4 1/2" set @ 3709'  
w/125 sx. Perf. 3584' - 3589'. D.V. tool set @ 1790' w/410 sx. cwc.  
Tested 8 5/8" to 300# cement @ surface. Squeezed 4 1/2" w/200 sx. cement  
blend w/500# hulls mixed in to Max. P.S.I. 900#. Close in P.S.I. 300#:  
Plug complete.

Remarks: \_\_\_\_\_

Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO

Bottom plug(in place): YES , CALC , NO  Dakota plug: YES  NO

Plugged through TUBING , CASING . Elevation: \_\_\_\_\_

I  did /  did not [ ] observe the plugging.

Carl Goodrow AUG - 2 1993

AK (agent)

DATE AUG 22 1993

TEL. NO. 38229

6-24 SEP 15 1993

FORM CP-2/3

82-93

STATE CORPORATION COMMISSION RECEIVED

INVOICED