

15-065-01696-00-02
R

6 030344

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER ~~15~~ 7-30-54 DRILLING DATE
NE, SEC. 27, T. 8 S, R 22 WE
_____ feet from ~~W~~/S section line
1650 feet from ~~W~~E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6718
Operator: FELL OIL & GAS COMPANY
Name & Address P.O. BOX 466
CHASE, KANSAS
67524

Lease Name FINK Well # 2 SWD
County GRAHAM 48.75
Well Total Depth 1500 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 160'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____
Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON CEMENT License Number _____
Address HAYS KANSAS

Company to plug at: Hour: PM Day: 20 Month: 11 Year: 19 84

Plugging proposal received from MELVIN BRADY

(company name) FELLOIL & GAS CO. (phone) _____

were: PUMP DOWN SKIM HOLE 2 3/8" TUBING - 50/50 PORE 6 3/4 GEL 3% CC
LOAD HOLE AND SQUEEZE.

RECEIVED
STATE CORPORATION COMMISSION
DEC 03 1984
DEC 03 1984

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Carl Goodnow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2:40 PM Day: 20 Month: 11 Year: 19 84

ACTUAL PLUGGING REPORT PUMP WATER TO CHECK RATE - BLEW HOLES IN 2 3/8 ABOVE
8 5/8 W. Q.W. - WELDED ON 8 5/8 COLLAR - COLLAR LEAK. W. O. W. - WELD ON PLATE AND
2 3/8 COLLAR - PUMP CEMENT MIX. - LOAD HOLE - PUMP 3 1/2 BBL/MIN AT 400'
SHOW RATE TO 1 BBL/MIN. AT 300' - TOTAL CEM. MIX. 300 SX. SHUT IN
WITH 200' ON HOLE WHICH HELD. PLUG DOWN @ 2:40 PM 11-20-84

Remarks: PLUG WELL DUE TO COMPLAINT AIF POLLUTION.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did / did not) observe this plugging.

DATE 12-12-84
INV. NO. 5947

Signed Carl Goodnow
(TECHNICIAN)

11-20

JAN 4 1985

11-30-84
FORM CP-2/3
Rev. 01-84