

API Number: 15-065-20,752-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SE NW NE /4 SEC. 27, 08, 22 W
4290 feet from S section line
1650 feet from E section line

Operator license# 31274

Lease: Fink Well # 1

Operator: R.L. Hrbek

County: Graham 122.53

Address: Rt. 1 - Box 11
Merino, CO 80741

Well total depth 3770 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 107 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 16 Month: May Year: 1997

Plugging proposal received from: R.L. Hrbek

Company: R.L. Hrbek Phone: 1997-5500-8

Were: Order 200 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.
Order sand and common cement.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 10:00 A.M., Day: 16 Month: May Year: 1997

Actual plugging report: 8 5/8" set at 107' cwc. 4 1/2" set at 3765'. Prod. Perf. 3412' - 3418'. Sanded back to 3360' with 4 sxs common cement on sand with bailer. Shots at 1756' - 1050' and recovered 680' of 4 1/2" casing. Pumped down 4 1/2" - 100 sxs cement with 400# hulls. Pulled to 300' and circulated with 60 sxs cement with 100# hulls. Pulled pipe. Hole full. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [X] observe the plugging.

Carl Goodrow (agent)

DATE JUN 06 1997

Form CP-2/3

INV. NO. 48237

5-16 JUL 22 1997