

S-16

4-032232

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-26815-00-00
150' W. of
N2 S2 NE /4 SEC. 27, 08, 22 W
3630 feet from S section line
1470 feet from E section line

Operator license# 31274

Lease: Fink Well # 2

Operator: R.L. Hrbek

County: Graham 122.27

Address: Rt. 1 - Box 11
Merino, CO 80741

Well total depth 3762 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 168 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 16 Month: May Year: 1997

Plugging proposal received from: R.L. Hrbek

Company: R.L. Hrbek Phone: -

Were: Order 200 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.
Order sand and common cement.

1997
Turn
3rd

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 12:00 P.M., Day: 16 Month: May Year: 1997

Actual plugging report: 8 5/8" set at 168'. 4 1/2" set at 3752'. O.H. 3752' - 3762'.
Sanded back to 3700' w/4 sxs common cement on sand with bailer. Shots at 1756' - 1050' and
680' recovered. Pumped down 4 1/2" with 60 sxs cement blend with 300# hulls mixed in to Max.
P.S.I. 1000#. Pulled casing. Hole full of cement. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [X] did not [] observe the plugging.

Carl Goodrow
(agent)

DATE JUN 06 1997

INV. NO. 48235

Form CP-2/3

S-16 JUL 22 1997