

7-15

4-032247

E-23,712-0001

API Number: 15-065-22,063 ~~00-00~~

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SE SE NW /4 SEC. 27, 08, 22 W
2970 feet from S section line
2970 feet from E section line

Operator license# 31274
Operator: Randy Hrbek
Address: Rt. 1 - Box 11
Merino, Colorado 80741

Lease: Fink Well # 5
County: Graham 123.01
Well total depth 3785 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 160 feet

Aband. oil well, Gas well, Input well , SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 15 Month: July Year: 1997

Plugging proposal received from: Randy

Company: Randy Hrbek Phone:

Were: Order 200 sxs 60/40 pozmix - 10% gel - 300# hulls - 12 sxs gel.

1997 July 21
KANSAS CORP COM

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All , Part [], None []

Completed: Hour: 3:15 P.M., Day: 15 Month: July, Year: 1997

Actual plugging report: 8 5/8" set at 160' cwc. 5 1/2" set at 3854' w/200 sxs.
D.V. at 1795' w/350 sxs cwc. Prod. Perfs at 3414' - 3500'. Squeezed 5 1/2" with 50 sxs
cement blend with 300# hulls mixed in, followed with 12 sxs gel, followed with 150 sxs
cement blend to Max. P.S.I. 1000#. S.I.P. 600#. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES , NO
Plugged through TUBING, CASING Elevation: GL

I did / did not [] observe the plugging.

Carl Goodrow
(agent)

INVOICED
JUL 22 1997
DATE
INV. NO. 48622
SEP 22 1997 -15