

6 030745

065-21933-00-00

API NUMBER 15-

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

N/2SW, SEC. 2, T 8 S, R 23 (W/2)

1980 feet from S section line

3450 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7107

Lease Name MONTGOMERY Well # 2

Operator Name & Address DAKOTA RESOURCES

County GRAHAM 122.53

Address 1700 LINCOLN ST. 3413 STE.

Well Total Depth 3770 feet

DENVER COLORADO

Conductor Pipe: Size _____ feet

80203

Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor GREAT BEND RABING License Number _____

Address (PHIL WAGNER) GREAT BEND KANSAS

Company to plug at: Hour: AM Day: 30 Month: 4 Year: 19 86

Plugging proposal received from MIKE GOMEZ

(company name) GREAT BEND CASING (phone) _____

were: 8 5/8 @ 280 w/ 200 SX 4 1/2 @ 3765 w/ 250 SX. PBTD 3755

ORDER SAND & COM. CMT. SHOOT & PULL PIPE ORDER 250 SX.

65/35 POL 10% GEL 2% DICEL (ECONOLITE) 5 SX. HULLS ALLIED CMT. CO.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:AM Day: 30 Month: 4 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND 50' ABOVE PERFS SPOT 4 SX. COM. CMT.

ON SAND W/BAILER. RECOVERED 1500' OF 4 1/2"

TIE ON TO 8 5/8 MIX. & Pump 4 SX. HULLS, 250 SX. ECONOLITE

CMT. MIX. + 1 SX. HULLS. MAX. PSTG 900# CLOSE IN 200#

Plug COMPLETE

STATE CORPORATION COMMISSION

JUN 16 1986

June 16 1986

19-86
6-13

Remarks: _____

(If additional description is necessary, use BACK of this form.)

INVOICED

(If you do not observe this plugging.

DATE JUN 18 1986

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 14158