

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-21, 703-00-00

NE, Sec. 4, T 8 S, R 23 WE

2310 feet from NS section line

2310 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

Lease Name Jones "C" Well # 1

Operator: Ritchie, A. Scott
Name & Address 125 N. Market, Suite 950
Wichita, Ks. 67202

County Graham

Well Total Depth 3790 feet

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8" feet 165

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co. License Number 611

Address 617 Union Center Bldg., Wichita, Ks. 67202

Company to plug at: Hour: 7:00 AM Day: 24 Month: 10 Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO Terry McRae

(company name) Murfin Drilling Co. (phone) 316-267-3241

were: Order out 170 sacks 50 posmix - 4% Gel. - 3% Cal. Cl. + 8 5/8" plug.
Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 2000' w/ 20 sacks,
2nd plug C 1150' w/ 80 sacks, 3rd plug C 200' w/ 40 sacks, 4th plug -
solid bridge of hulls + plug C 40' w/ 10 sacks.

Circulate 10 sacks in rat hole & 10 sacks in mouse hole.

Signed [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:45 AM Day: 24 Month: 10 Year: 19 82

ACTUAL PLUGGING REPORT 8 5/8" - 165' S.C. cas. w/ 145 sacks common - 2% Gel. - 3% Cal. Cl.

Ordered 170 sacks 50 posmix - 4% Gel. - 3% Cal. Cl. + 8 5/8" plug. Spot w/ drill
stem w/ heavy mud between all plugs. 1st plug C 2000' w/ 20 sacks,
2nd plug C 1150' w/ 80 sacks, 3rd plug C 200' w/ 40 sacks, 4th plug -
solid bridge of hulls + plug at 40' w/ 10 sacks.

Circulated 10 sacks in rat hole & 10 sacks in mouse hole.

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION

NOV 08 1982

CONSERVATION DIVISION
Wichita, Kansas

11-8-82

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

Signed [Signature] (TECHNICIAN)

INVOICED
11-24-82
1705 EW