

6 030432

15065-20724-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
NWSUSA, SEC. 5, T 8 S, R 23 WP
990 feet from ~~25~~ section line
4950 feet from ~~18~~ section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5198
Operator: a Scott Ritchie
Name & Address: 125 N Market St, 950
Wichita, Kansas
67202

Lease Name Montgomery Well # 1
County Graham 122.43
Well Total Depth 3767 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 128

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Poe Well Service License Number 935
Address Hill City Kansas

Company to plug at: Hour: AM Day: 24 Month: 4 Year: 19 85

Plugging proposal received from Tom Post
(company name) A Scott Ritchie (phone) _____

were: 8 5/8 act @ 128 w/ 150 ap 4 1/2 act @ 3767 w/ 100 ap Perfs @ 3721-23 1/2
no pipe recovered hole in casing - spot with tubing cement and
gel plugs and squeeze casing - casing squeezed twice before
with 200 ap 60/40 3bcc - Order 250 ap 50/50 ap 6% gel 3bcc 20 ap
gel. 3 ap hells. 4 1/2 WP. Allied Cem. Co.

Plugging Proposal Received by Carl Goodlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 4:30 PM Day: 24 Month: 4 Year: 19 85

ACTUAL PLUGGING REPORT Tagged sand @ 3720 with tubing displaced 50 ap
Cem. mix laydown pipe to 2980' displace 50 ap Cement mix laydown
tubing to 2140' displace 50 ap Cement mix laydown tubing to
1400' displace 30 ap Cement mix 3 ap gel circulated Cement.
Pump down backside 10 ap Cement 17 ap gel 2 ap hells. 50 ap
mix pressure to 250# - Pump on 4 1/2 Squeeze 50 ap Cement mix to 1800 max.

Remarks: Shut in Plug complete
(If additional description is necessary, use BACK of this form.)
I (did / did not) observe this plugging.

DATE 5-14-85
INV. NO. 8140

Signed Carl Goodlow (TECHNICIAN) 5-10-85 mps

4-24 JUN 6 1985 JUL 1 8 1985

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1985
5-10-85
CONSERVATION DIVISION
Wichita, Kansas