

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20025-00-00  
Spot: CNENW Sec/Twnshp/Rge: 7-8S-23W  
3300 feet from S Section Line, 4620 feet from E Section Line  
Lease/Unit Name: MONTGOMERY A Well Number: 2  
County: GRAHAM Total Vertical Depth: 3795 feet

Operator License No.: 31274  
Op Name: HRBEK, R.L.  
Address: RR 1, BOX 11  
MERINO, CO 80741

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 314  
Production: Size 5.5 feet: 3793  
Liner: Size \_\_\_\_\_ feet:

*5123.34*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/27/2001 12:00 PM

Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.

Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 8 yards Redi-Mix - 6 sxs common with sand/yard.

Plugging Proposal Received By: CARL GOODROW  
Date/Time Plugging Completed: 04/27/2001 2:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 314' w/250 sxs cwc. 5 1/2" set at 3793' with D.V. Tool at 1986' with total of 475 sxs cwc.  
Prod. Perfs 3727' - 3756'.  
Fluid level low.  
Filled 5 1/2" with 8 yards Redi-Mix.  
Plug complete.

INVOICED

DATE 5-29-01

INV. NO. 2001061842

KANSAS CORPORATION  
MAY 22 2001  
5-22-2001  
CONSERVATION

Remarks:

Plugged through: CSG

District: 04

Signed

*Carl Goodrow*

(TECHNICIAN)

~~CITIES SERVICE OIL COMPANY~~ #2 MONTGOMERY 'A' 7-8-23W  
 C NE NW  
 Contr. GARVEY DRLG Cty. GRAHAM  
 Geol. \_\_\_\_\_ Pool GETTYSBURG  
 E. 2298 KB Cm. 3/29/67 Cp. 5/25/67 IP PMP 93' BOPD/NW  
LANS 3727-56


SMP Tops	Depth	Datum	Csg.
			API 15-065-20,025
			8" 314/250 sx; 5" 3793 & DU @
			1986 W/475 SX.
			DST 3582-3618/30", 50' DM, NS,
			BHP 90-530#; FP30-90#;
			DST 3623-45/1', 100' GIP, 108'
			V OILY GSY M, 100' MDY OIL,
			40' OILY MW, 20' WTR, BHP
			730-720#/30", FP 60-126#;
			DST 3674-3723/90", 173' OILY GSY
			MD, 100' OILY M, 20' MDY OIL,
			BHP 1031-860#/30", FP 70-160#
			PF 12/3727-56, 10/3750-56, 10/
			3727-32, PMP 15 BO/NW/24 HRS, PMP
			8 BO/NW/24 HRS, OFF PMP, A 50
			(3750-56) CHANNELLED, RESET PKR,
			A 2950 (PF 3727-56), PMP 30 BO +
			104 BW/24 HRS, 93 BO/NW/24 HRS.
HEEB	3518	-1220	
TOR	3544	-1246	
LKC	3561	-1263	
BKC	3773	-1475	
TD	3795	-1497	

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS