

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21459-00-01
Spot: CW2NE Sec/Twnshp/Rge: 7-8S-23W
3960 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: MONTGOMERY A Well Number: 3
County: GRAHAM Total Vertical Depth: 3775 feet

Operator License No.: 30163
Op Name: GREAT PLAINS PETROLEUM, INC.
Address: 221 CIRCLE DRIVE
WICHITA, KS 67218

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 371
Production: Size 4.5 feet: 3774
Liner: Size _____ feet:

\$122.69

Well Type: EOR UIC Docket No: E24867.1 Date/Time to Plug: 04/27/2001 3:00 PM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 8 yards Redi-Mix.

Plugging Proposal Received By: CARL GOODROW
Date/Time Plugging Completed: 04/27/2001 4:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 371' w/250 sxs cwc. 4 1/2" set at 3774' w/350 sxs.
D.V. Tool set at 1929' w/375 sxs cwc.
Prod. Perfs 3636' - 3694'.
Fluid level 3200'.
Filled 4 1/2" with 8 yards Redi-Mix (10 yards by yield).
Plug complete.

INVOICED
DATE 5-31-01
INV. NO. 2001061868

RECEIVED
STATE CORPORATION COMMISSION
MAY 31 2001
5-31-2001
CONSERVATION DIVISION

Remarks:

Plugged through: CSG

District: 04

Signed Carl Goodrow
(TECHNICIAN)

NO.

MAY 02 2001

PETROLEUM CORPORATION OF TEXAS

#3 MONTGOMERY "A"

7-B-23W
C W/2 NE

BOX 911

BRECKENRIDGE, TX 76024

CONTR ABERCROMBIE DRILLING INC CTV GRAHAM

GEOL ROGER WELTY

FIELD GETTYSBURG

K 2234 KB CM 9/11/81

CARD ISSUED 1/7/82

IP P 13.55 BO & 20.33

BWPD, LKC 3636-94 OA

2229 GL
API 15-065-21,459

+	+
+	+

LOG	TOPS	DEPTH	DATUM
ANH		1891	+ 343
B/ANH		1921	+ 313
HEEB		3460	-1226
TOR		3485	-1251
LANS		3500	-1266
MUNCIE CR		3614	-1380
B/KC		3710	-1476
RTD		3775	-1541
LTD		3783	-1549

B 5/8" 371.5/250sx; 4 1/2" 3774

NO DSTS
MICT - CO, PF 3688-94, 3668-73, 3655-
58, 3636-40, AC2000G, SWB LD, POP,
P 13.55 BO & 20.33 BWPD, 10/27/81

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS