

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22432-00-00
Spot: CNWNWSE Sec/Twnshp/Rge: 7-8S-23W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: MCVEY-ROSS A Well Number: 2
County: GRAHAM Total Vertical Depth: 3804 feet

Operator License No.: 9449
Op Name: GREAT EASTERN ENERGY & DEV. COR
Address: 500 W. TEXAS STE 955
MIDLAND, TX 79702

Conductor Pipe: Size _____ feet: 8/23.63
Surface Casing: Size 8.625 feet: 227 140 sxs cmt
Production: Size 4.5 feet: 3802 400 sxs cmt
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/02/2002 8:00 AM
Plug Co. License No.: 9449 Plug Co. Name: GREAT EASTERN ENERGY & DEV. CORP.
Proposal Rcvd. from: MICHEAL DAVIGNON Company: GREAT EASTERN ENERGY & DEV. Phone: (785) 623-7520

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/02/2002 10:00 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Squeezed 4 1/2" casing as follows:
25 sxs cement with 200# hulls - 11 sxs gel.
145 sxs cement with 200# hulls.
Max. P.S.I. 850#. S.I.P. 500#.
Squeezed 8 5/8" S.P. - 10 sxs cement with 100# hulls.
Max. P.S.I. 700#.

RECEIVED
APR 15 2002
4-15-2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

10

Signed

Dennis L. Hamel

(TECHNICIAN)

INVOICED

Form CP-2/3

APR 04 2002

DATE 4-16-02
INV. NO. 2002061656

replacement card

DCF EXPLORATION
LAKEWOOD, CO 80215

7-08 -23W
NW NW SE

#2 MCVEY-ROSS "A"

site: 1-1/4 N & 2-1/8 E OF PENOKEE, KS	cty: GRAHAM	API 15-065-22432
contr: RED TIGER DRILLING COMPANY	field: GETTYSBURG	
geol: RON NELSON		
fr date 12/18/87	spd date 01/16/88	drig comp 01/25/88
	card issued 03/02/88	last revised 06/22/88

ELV: 2302 KB LOG

tops.....	depth/datum
ANH.....	1954 +348
B/ANH.....	1984 +318
TOP.....	3304 -1002
HEEB.....	3510 -1208
TOR.....	3540 -1238
LANS.....	3553 -1251
BKC.....	3762 -1460
LTD.....	3803 -1501
RTD.....	3804 -1502

IP status:
 OIL, P 90 BOPD, NW, LKC 3679-3685,
 CORRECTION: 6/22/88 - ORIGINALLY FIRST REPORTED
 IN C N/2 NW SE
 CSG: 8-5/8" 227 / 140 SX, 4-1/2" 3802 / 400 SX
 NO CORES
 DST (1) 3656-3710 (LANS H,I), / 30-45-30-45, 1300' GIP,
 REC 900' CLEAR GSY OIL, 180' VHO & GCM, 120' MW
 ISIP 819# FSIP 781# IFP 136# -271# FFP 368# -486#
 IHP 1951# FHP 1922#
 DST (2) 3696-3730 (LANS J), / 30-30-15-0, REC 10' M,
 W / GSO & GAS ODOR ISIP 0# IFP 58# -58# FFP 58#
 -58# IHP 2060# FHP 2030#

DCF EXPLORATION
LAKEWOOD, CO 80215

7-08 -23W
NW NW SE

#2 MCVEY-ROSS "A"

DST (3) 3729-3763 (LANS K), / 30-30-0-0, REC 20' M ISIP 397# IFP 39# -39# IHP 1981# FHP 1893#
 MICT - CO, PF (LANS H) 3679-3685, W / 4 SPF, SWB 7.51 BO, NW / 60", 7.02 BO, NW / NX 60",
 NAT, AC 500 GAL (15% NE), SWB LD, SO, RE-AC 1500 GAL (20% NE), SWB LD & REC 11.05
 BOPH, NW, POP, P 90 BOPD, NW, 2/10/88