


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Graham County. Sec. 7 Twp. 8S Rge. (E) 23 (W)
Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner Peel-Hardman Oil Operators
Lease Name McVey-Ross Well No. 1
Office Address R. R. #3, Box #144B, Wichita 15, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 7, 1958
Application for plugging filed August 7, 1958
Application for plugging approved August 7, 1958
Plugging commenced August 7, 1958
Plugging completed August 7, 1958
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricus
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3729 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	186'	8 5/8"	186'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- From 3729' to 600' - Heavy Rotary Mud
- " 601 1/2 to 600' - Wooden Plug
- " 600' to 498' - 25 sacks cement
- " 498' to 186 1/2' - Heavy Rotary Mud
- " 186 1/2' to 185' - Wooden Plug
- " 185' to 139' - 15 sacks cement
- " 139' to 41 1/2' - Heavy Rotary Mud
- " 41 1/2' to 40' - Wooden Plug
- " 40' to 6' - 10 sacks cement
- " 6' to surface - Cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF Kansas, COUNTY OF Sedgwick, ss.
William Herbert (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William Herbert

R. R. #3, Box #144B, Wichita 15, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of August, 19 58

My commission expires March 4, 1962

Marion M. Herbert
Notary Public.

PLUGGING
FILE SEC. 7 T 8 R23W
BOOK PAGE 122 LINE 43

ALL INFORMATION CONTAINED
HEREIN IS UNCLASSIFIED
DATE 8-13-1958
BY SP-5 J. D. VISION

DRILLERS LOG

Company: Peel-Hardman Oil Operators

SE-SE-SE
Sec. 7-8S-23W

Farm: McVey-Ross Well No. 1

County: Graham,
Kansas

Total Depth: 3729'

Comm. 7-31-58 Comp: 8-7-58
Contractor: Glenn W. Peel Drilling Co.

Elevation:

Casing: 8 5/8' @ 186' Cem.

Production: Dry

Figures below indicate bottom of formation

Surface Clay	0'	40'
Sand and Clay		128
Shale		1000
Sand w/shale streaks		1180
Shale		1250
Sand and shale		1580
Shale		1890
Anhydrite		1921
Red Bed		2100
Shale		2740
Lime		2980
Shale		3125
Shale w/lime streaks		3255
Lime and Shale		3345
Lime		3729
Total Depth		3729

This is to certify that the above information is to the best of my knowledge true and correct .

GLENN W. PEEL DRILLING CO.

BY: *Glenn W. Peel*

SUBSCRIBED AND SWORN TO before me this 12th day of August, 1958.

My commission expires March 4, 1962

Marion McHerbert
Notary Public

PLUGGING
FILE SEC. <u>7</u> T. <u>8</u> R. <u>23W</u>
BOOK PAGE <u>122</u> LINE <u>43</u>

STATE OF KANSAS
 AUG 13 1958
 CONSTRUCTION
 Wichita, Kan.