

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-01932-

LEASE NAME Montgomery

WELL NUMBER A-1

SPOT LOCATION 330 N & 330' W/C

SEC. 7 TWP. 8 RGE. 23 (E) or (W)

COUNTY Graham

Date Well Completed 9/ 1941

Plugging Commenced 8/28/84

Plugging Completed 8/28/84

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Damson Oil Corporation

ADDRESS P. O. Box 750, Amarillo, Texas 79105

PHONE # (405) 840-1661 OPERATORS LICENSE NO. 8098

Character of Well Oil
(Oil Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Carl Goodrow (District Plugger)

Is ACO-1 filed? Unknown If not, is well log attached? No

Producing formation LKC Depth to top 3588 bottom 3756 T.D. 3765

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				4 1/2	3825'	None
				8 5/8	310'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Mixed 2 sacks gel & 3 sacks of hulls, followed by 60 sacks of 50/50 poz, 6% gel, 3% C.C., 5 sacks gel, 50 sacks cement, 5 sacks gel, 50 sacks cement. Maximum pressure 400# and shut-in. Pumped 50 sacks down annulus at 200 lbs. pressure and shut-in. Finished at 11:00 A.M. on 8/28/84.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pfeifer-Sharpe, Inc. License No. 6967

Address P. O. Box 386


Hill City, Kansas 67642

STATE OF Kansas COUNTY OF Graham, ss.

Bill Daily (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.

(Signature) Bill Daily

(Address) Hill City, Kansas



RECEIVED
AUG 30 1984
8-30-1984
CONSERVATION DIVISION
SUBSCRIBED AND SWORN TO before me this 28th day of August, 1984

Debra L Pfeifer-Wente
Notary Public

My Commission expires: May 12, 1986