

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-065-21,850-00-00

LEASE NAME Bethell

WELL NUMBER #1

SPOT LOCATION 300' N 100' W NE SE NE

SEC. 17 TWP. 8S RGE. 23W (E) or (W) (W)

COUNTY Graham

Date Well Completed \_\_\_\_\_

Plugging Commenced 3-12-86

Plugging Completed 3-20-86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Mid Continent Energy Corporation

ADDRESS 120 S. Market Suite 712 Wichita, Ks. 67202

PHONE # (316) 265-9501 OPERATORS LICENSE NO. 5205

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3665'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	325'	none
				4-1/2"	3661'	1503'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged off bottom with sand to 3400' and 4 sacks cement. Shot pipe @2518', 2030', 1811', 1623', 1503', pulled 37 jts. 4-1/2" casing. Hooked onto surface and pumped 2 sacks hulls, pressured up to 1800 lbs. Washed down w/drill pipe to 1200', set plug @1200' w/100 sks, set plug @800' w/100 sks, plug @400' w/100 sks filled surface w/50 sks 60/40. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling

Address Box 347 Chase, Kansas 67524

License No. 6050 Pos. 6% gel  
Plugging Complete.

STATE OF Kansas COUNTY OF Rice, ss.


R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 14th day of May, 19 86

My Commission expires: \_\_\_\_\_



Irene Hoover  
Notary Public

STATE CORPORATION COMMISSION  
MAY 16 1986  
CONSERVATION DIVISION  
Wichita, Kansas