

15-065-00949-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Graham County, Sec. 18 Twp. 8 Rge. 23 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE NE SE
Lease Owner Leo J. Dreiling
Lease Name Higer Well No. 2
Office Address Victoria, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 6-30 19 57
Application for plugging filed 6-30 19 57
Application for plugging approved 6-30 19 57
Plugging commenced 6-30 19 57
Plugging completed 6-30 19 57
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3730 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	211'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 650'. Set plug & spotted 25 Sacks of cement through drill pipe. Filled hole to 40' with heavy mud, set plug & 1/2 sack of hulls, mixed & poured 10 sacks of cmt. in pipe.

STATE CORPORATION COMMISSION
JUL 3 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Leo J. Dreiling Oil Company 7-3-57
Address Victoria, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
V. D. Sidey (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. D. Sidey
P. O. Box 387 Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of July, 19 57

My commission expires September 17, 1960
Marguerite Byrne Notary Public.

28-3273-s 4-50-10M

PLUGGING
FILE SEC 18 T 8 R 23W
BOOK PAGE 24 LINE 28


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- LEO J. DREILING
 Farm- Higer "B" No. 2

SEC. 18 T. 8 R. 23W
 SE NE SE

Total Depth. 3735'
 Comm. 6-21-57 Comp. 7-12-57
 Shot or Treated.
 Contractor. V. D. Sidey Oil Co.
 Issued. 9-13-58

County Graham
 KANSAS



CASING:
 8 5/8" 211'

Elevation. 2187' RB

Production. Dry

Figures Indicate Bottom of Formations.

shale	211
shale	500
shale & shells	940
sand & shale	1000
shale & shells	1175
sand	1200
shale-limestone	1300
shale	1480
sand & shale	1638
red bed	1810
red bed & shale	1883
Anhydrite	1930
shale & shells	2300
shale & shells	2490
lime & shale	2570
lime & shale	2890
lime & shale	2975
lime	3050
lime & shale	3130
shale	3215
lime	3235
lime	3495
lime & shale	3565
lime	3670
lime	3735

Total Depth

TOPS: SCOUT	
Heebner	3494
Lansing	3534

RECEIVED
 STATE CORPORATION COMMISSION

NOV 3 1964

CONSERVATION DIVISION
 Wichita, Kansas

15-069-00949-06-00

SIDEY DRILLING CO.

BUILDING & LOAN BLDG. P. O. BOX 387
RUSSELL, KANSAS

Company **LEO J. DREILING OIL COMPANY**

Sec. 18 T. 8 R. 23W
Loc. **SE NE SE**

Farm **HIGER** No. 2

Total Depth **3730' RTD**
Comm. **6-20-57** Comp. **6-30-57**
Shot or Treated
Contractor **Sidey Drilling Company**
Issued

County **Graham**

Casing
20
15½
12½
13%
10
8¼ 211'
6%
5 5/16

Elevation **2185 DF**

Production **D & A**

Figures Indicate Bottom of Formations

0-211	Shale
211-500	Shale
500-940	Shells & shale
940-1000	Sand & shale
1000-1175	Shale & shells
1175-1200	Sand
1200-1300	Shale & lime streaks
1300-1480	Shale
1480-1555	Sand
1555-1600	Shale
1600-1638	Sand
1638-1810	Red bed
1810-1883	Red bed & shale
1883-1930	Anhydrite
1930-2065	Shale & shells
2065-2300	Shale & shells & red bed
2300-2490	Shale & shells
2490-2500	Lime
2500-2975	Lime & shale
2975-3050	Lime
3050-3130	Lime & shale
3130-3215	Shale
3215-3235	Lime
3235-3350	Shale & lime
3350-3495	Lime
3495-3565	Lime & shale
3565-3670	Lime
3670-3730	Lime RTD

RECEIVED
STATE CORPORATION COMMISSION
JUL 3 1957
CONSERVATION DIVISION
Wichita, Kansas
7-3-57

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

I, V. D. Sidey, of the Sidey Drilling Company, upon oath states that the above and foregoing is a true and correct copy of the log from the Daily Drilling Report on your Higier "B" #2 Well.

V. D. Sidey
V. D. Sidey

Subscribed and sworn to before me this 2nd day of July, 1957.

Marquitta Byrne
NOTARY PUBLIC

My Commission Expires: September 17, 1960

PLUGGING
FILE SEC 18 T 8 R 23W
BOOK PAGE 24 LINE 28