

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15-065-21762-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Graham SEC. 18 TWP. 8S RGE. 23 E/W
 Location as in quarters or footage from lines:
SE SW SE

Locate Well
 correctly on above
 Section Platt.

Lease Owner N-B Company, Inc.
 Lease Name Higer Well No. 3
 Office Address P. O. Box 506, Russell, KS 67665-0506
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed 3-3-83
 Application for plugging filed 3-3-83
 Plugging commenced 3-3-83
 Plugging completed 3-4-83
 Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3734'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	266'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Mud laden fluid @ 3734' - 1970'
 20 sks cement @ 1970'
 100 sks cement @ 1050'
 40 sks cement @ 270'
 10 sks cement @ 40'
 10 sks cement in rathole.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Emphasis Oil Operations

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Joe K. Branum (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Joe K. Branum
P. O. Box 506, Russell, KS 67665-0506
 (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 19 83



Glenda R. Tiffin
 Glenda R. STATE CORPORATION COMMISSION

My Commission expires: February 6, 1984.

MAR 9 1983
 3-9-83
 CONSERVATION DIVISION
 Wichita, Kansas

15-065-21762-00-00

EMPHASIS OIL OPERATIONS

P. O. Box 506

Russell, Kansas 67665-0506

DRILLERS LOG

OPERATOR: N-B Company, Inc.
P. O. Box 506
Russell, Kansas 67665-0506

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506
Russell, Kansas 67665-0506

LEASE: Higer WELL: #3

LOCATION: SE SW SE
Section 18-8S-23W
Graham County, Kansas

Total Depth: 3734'
Commenced: 2-24-83
Casing: 8-5/8" @ 266' with 150 sks cement

Elevation: 2194' K.B.
Completed: 3-3-83
Status: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Topsoil & Sand	40'	Anhydrite	1935'
Sand & Shale	269'	Shale & Sand	2320'
Shale	570'	Shale & Lime	3357'
Sand & Shale	1901'	Lime (R.T.D.)	3734'

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

Joe K. Branum

Joe K. Branum

RECEIVED
STATE CORPORATION COMMISSION


MAR 9 1983

CONSERVATION DIVISION
Wichita, Kansas

3-9-83

Subscribed and sworn to before me this 8th day of March, 1983.

My Commission Expires: February 6, 1984.



Glenda R. Tiffin

Notary Public