

15-065-02327-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 19 Twp. 8 Rge. 23 (E) (W)

Location as "NE/CNW%SW%" or footage from lines NE SW NE

Lease Owner Leo J. Dreiling

Lease Name Brinkmeyer Well No. 2

Office Address Victoria, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 6-12 1957

Application for plugging filed 6-12 1957

Application for plugging approved 6-12 1957

Plugging commenced 6-12 1957

Plugging completed 6-12 1957

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Hays, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3806 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	197'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 650'. Set plug and spotted 25 Sacks of cement through drill pipe. Filled hole to 40' and set plug and 1/2 Sack of Hulls. Mixed and poured 10 Sacks of cement bringing cement to top of surface pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sidey Drilling Company 6/19/57

Address Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss. V. D. Sidey (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. D. Sidey

P. O. Box 387 Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of June, 19 57

My commission expires September 17, 1960

Marguerite Byrne  
Marguerite Byrne Notary Public.

PLUGGING  
FILE SEC. 19 T. 8 R. 23W  
BOOK PAGE 21 LINE 16

15-065-02327-0000

# SIDEY DRILLING CO.

BUILDING & LOAN BLDG. P. O. BOX 387

RUSSELL, KANSAS

Company **LEO J. DREILING OIL COMPANY**  
Farm **Brinkmeyer** No. **2**

19 8 23W  
Sec. **NE SW NE** R.  
Loc.

Total Depth **3806'**  
Comm. **6-1-57** Comp. **6-12-57**  
Shot or Treated  
Contractor **Sidey Drilling Company**  
Issued

**Graham**  
County

Casing  
20 10 197'  
15½ 8¼  
12½ 6¾  
13% 5 5/16

Elevation **D & A**  
Production

Figures Indicate Bottom of Formations

0-197	Cement
197-440	S. shale & shale
440-700	Shale & shells
700-880	Shale
880-950	Shale sand
950-1150	Shale shells
1150-1285	Sand shale
1285-1445	Shale
1445-1460	Sand
1460-1485	Shale
1485-1648	Sand
1648-1725	Red bed
1725-1936	Red bed & shale
1936-1950	Anhydrite
1950-1985	Anhydrite
1985-2340	Shale & shells
2340-2430	Shale & lime
2430-2570	Shale shells
2570-2665	Lime
2665-2870	Lime & shale
2870-2905	Lime
2905-3010	Lime & shale
3010-3090	Shale lime streaks
3090-3415	Lime & shale
3415-3465	Lime
3465-3540	Lime & shale
3540-3715	Lime
3715-3740	Lime
3740-3806	Lime RTD

RECEIVED  
6/19/57

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

I, V. D. Sidey, of the Sidey Drilling Company, upon oath states that the above and foregoing is a true and correct copy of the log from the Daily Drilling Report on your Brinkmeyer #2 Well.

*V. D. Sidey*  
V. D. Sidey

Subscribed and sworn to before me this 18th day of June, 1957.

*Marguerite Bynum*  
NOTARY PUBLIC

My Commission Expires: September 17, 1960

PLUGGING  
FILE SEC. 19 T. 8 23W  
BOOK PAGE 21 LINE 16