

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: HIZEY SERVICE & SUPPLY, INC.
Address: P.O. BOX 296 AUGUSTA, KS. 67010
Phone: (316) 775-5496 Operator License #: 32444
Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 12/18/07 (Date)
by: DUANE KRUEGER/JEFF KLOCK/BILL JOHNSON (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
MISSISSIPPI Depth to Top: 2455 Bottom: 2460 T.D. 2519

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 015-22101 - 00-00
Lease Name: ED LIGGETT
Well Number: #4
Spot Location (QQQQ): SW - NE - SW -
1650 Feet from North / South Section Line
3630 Feet from East / West Section Line
Sec. 6 Twp. 23 S. R. 4 East West
County: BUTLER
Date Well Completed: _____
Plugging Commenced: _____
Plugging Completed: 12/19/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
MISSISSIPPI	OIL/WATER	0	2455	4 1/2"	2519	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

MOVED IN FOUND TUBING PARTED AT 115', CIRCULATE HOLE GOT TO 265' WITH 1" TUBING, RAN SPEAR TUBING WAS HUNG IN HOLE THEN RAN TAPPER TAP, COULD NOT MOVE, WENT INSIDE TUBING SHOT OFF AT 265' PULLED OUT, PERFERATED 4 1/2" CASING AT 260, RAN 1" TO 260' RIGGED CONSOLIDATED UP AND PUMPED CEMENT UP BACKSIDE THEN PULLED 2 JOINTS OF 1" AND PUMPED CEMENT INSIDE 4 1/2" TO SURFACE AS PER JEFF KLOCK INSTRUCTIONS. CONSOLIDATED TICKET #13391

Name of Plugging Contractor: BPC WELL PLUGGING License #: 32475
Address: 10139 SW HAVERHILL RD. AUGUSTA, KS. 67010

RECEIVED
KANSAS CORPORATION COM

Name of Party Responsible for Plugging Fees: HIZEY SERVICE & SUPPLY, INC.

JAN 23 2008

State of KANSAS County, BUTLER, ss.


CONSERVATION DIVISION
WICHITA, KS

MICHAEL W. KISER

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Michael W. Kiser

(Address) P.O. BOX 296 AUGUSTA, KS. 67010



SUBSCRIBED and SWORN TO before me this 16th day of January, 2008

Mary E. Williams
Notary Public

My Commission Expires: 4-1-10.

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PK