

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Nadel and Gussman, L.L.C
Address: 15 E. 5th St., Suite 3200, Tulsa, OK 74103
Phone: (918) 583-3333 Operator License #: 32638
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: _____ (Date)
by: Eric MacClaren (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All *(If needed attach another sheet)*

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-129-20008-0001
Lease Name: Williams
Well Number: 1-34
Spot Location (QQQQ): C - SE - NW - NW
990 4182 Feet from North / South Section Line
990 4365 Feet from East / West Section Line
Sec. 34 Twp. 31 S. R. 42 East West
County: Morton
Date Well Completed: 3/8/02
Plugging Commenced: 4/19/07
Plugging Completed: 4/20/07

KCC
PICT
per
COPS

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	1425	-
				4-1/2	3241	1750

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
Mixed 400# hulls & 20 sx cmt plug @ perfs from 2778 to 2578. Circ 4-1/2 w/mud above plug thru 2-3/8. 4-1/2 parted @ 1750.
Pulled 4-1/2 & ran 2-3/8 to 1450. Circ hole w/mud & mixed 50 sx 1450 to 1300. 40 sx 460 to 340. 10 sx 40 to 0. Capped
8-5/8 3 ft below GL.


RECEIVED
KANSAS CORPORATION COMMISSION
JAN 22 2008
CONSERVATION DIVISION
WICHITA, KS

Name of Plugging Contractor: Sargent and Horton Plugging, Inc. License #: 31151
Address: Rt. 1, Box 49 BA, Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: Nadel and Gussman, LLC
State of Oklahoma County, Tulsa, ss.

James Piland, Manager of Production (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 15 E. 5th St., Suite 3200, Tulsa, OK 74103
SUBSCRIBED and SWORN TO before me this 17 day of January, 20 08
[Signature] My Commission Expires: 8-1-11
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]