

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21613-00-00
Spot: SWSW Sec/Twnshp/Rge: 1-35S-15W
660 feet from S Section Line, 660 feet from W Section Line
Lease Name: Z BAR RANCH Well #: 3-1
County: BARBER Total Vertical Depth: 5010 feet

Operator License No.: 3372
Op Name: DIXON ENERGY, INC.
Address: 8100 E 22ND N BLDG 1600 SUITE C
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	5008	0	WITH 125 SX CMT
SURF	8.625	936		WITH 350 SX CMT <u>162.83</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/14/2008 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: MIKE DIXON Company: DIXON ENERGY Phone: (316) 264-9632

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/16/2008 2:30 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

PUMPED 200# HULLS & 75 SX CMT. DISPLACED TO BOTTOM. SHUT IN PRESSURE 1400#. PARTIAL CASING COLLAPSE AT 523'. 2ND PLUG PERFORATED CASING AT 505' WITH 4 SHOTS-ESTABLISHED RATE AT 1.5 BBLS PER MINUTE AT 800#. PUMPED 220 SX CMT. DID NOT CIRCULATE. SDON. TOC @ 114'. TOPPED OFF WITH 3 YARDS OF REDI-MIX.

Perfs:

Top	Bot	Thru	Comments
4985	4994		

INVOICED
DATE 1-23-08
INV. NO. 2008061092


Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 22 2008

District: 01



Signed Steve Durrant

(TECHNICIAN)

CONSERVATION DIVISION
WICHITA, KS

PKY