

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20465-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 9-33S-19W
⁴⁹⁷²
~~4950~~ Feet from S Section Line, ²⁶¹⁰ feet from E Section Line
Lease Name: JELLISON C ²³⁹⁴ Well #: 1-9
County: COMANCHE Total Vertical Depth: 5330 feet

KCC PCT PERFS

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S MAIN STE 420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4980		WITH 4 SX CMT
CIBP		5070		
CIBP		5100		
PROD 4.5		5305	3000	WITH 200 SX CMT
SURF 8.625		642		WITH 500 SX CMT

173-23

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/11/2008 11:59 AM
Plug Co. License No.: 33645 Plug Co. Name: PLAINS, LLC
Proposal Rcvd. from: ROBIN BROWN Company: LOTUS OPERATING Phone: (620) 546-4801

Proposed Plugging Method: CIBP ABOVER PERFS & 4 SX CMT. PLUG AT 940' WITH 10 SX GEL & 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/11/2008 1:10 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4980' WITH 4 SX CMT. 1ST PLUG AT 940' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5136	5228		MISS
5025	5033		PAWNEE

INVOICED
DATE 1-23-08
INV. NO. 2008061102

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 17 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED
JAN 14 2008
KCC Dodge City

Signed Eric MacLaren
(TECHNICIAN)