

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-137-20473-00-00  
Spot: NWSWNW Sec/Twnshp/Rge: 1-3S-24W  
1890 feet from N Section Line, 660 feet from W Section Line  
Lease Name: SCHULTZE Well #: 1-1  
County: NORTON Total Vertical Depth: 3642 feet

Operator License No.: 33335  
Op Name: IA OPERATING, INC.  
Address: 9915 W 21ST ST, STE B  
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	241		

118.37

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/12/2008 10:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: ANDY DINKEL Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.  
Drilled out of LKC into granite.  
No ar buckle found.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE  
Date/Time Plugging Completed: 01/12/2008 12:30 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 1950' w/25 sxs.  
2nd. Plug at 1275' w/100 sxs.  
3rd. Plug at 300' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Perfs:

INVOICED  
DATE 1-23-08  
INV. NO. 2008061098


RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 17 2008  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed \_\_\_\_\_

  
(TECHNICIAN)

Form CP-2/3

JAN 14 2008

