

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-085-20077-00-00  
Spot: NENESW Sec/Twnshp/Rge: 27-6S-13E  
2310 feet from S Section Line, 2310 feet from W Section Line  
Lease Name: CLYDE RIESCHICK Well #: 1  
County: JACKSON Total Vertical Depth: 3460 feet

Operator License No.: 6039  
Op Name: L.D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	350		

112.45

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/13/2007 8:00 AM  
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.  
Proposal Rcvd. from: TIM GULICK Company: C & G DRILLING, INC. Phone: (620) 583-4306

Proposed Plugging Method: 50' PLUG OF CEMENT AT TD, 50' PLUG OF CEMENT AT 2835', 50' PLUG AT 2489' AND CIRCULATE CEMENT FROM 350' TO SURFACE.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE  
Date/Time Plugging Completed: 08/13/2007 12:00 AM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

HAD DRILL PIPE SET AT 3410' AND SPOTTED 15 SACKS OF CEMENT. PULLED DRILL PIPE TO 2835' AND PUMPED 15 SACKS OF CEMENT. PULLED DRILL PIPE TO 2489' AND PUMPED 15 SACKS OF CEMENT. PULLED DRILL PIPE TO 350' AND CIRCULATED 140 SACKS OF CEMENT TO SURFACE. PLUGGED RATHOLE WITH 15 SACKS OF CEMENT AND PLUGGED MOUSEHOLE WITH 15 SACKS OF CEMENT.

Perfs:

RECEIVED  
KCC DISTRICT #3  
JAN 10 2008 TCH  
CHANUTE, KS

INVOICED  
DATE 1-23-08  
INV. NO. 2008061107

RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 18 2008  
CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: DP

District: 03

Signed Taylor C. Hourman  
(TECHNICIAN)

*[Handwritten signature]*