

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21415-00-00
Spot: E2NWNWSW Sec/Twnshp/Rge: 29-32S-10W
2970 feet from N Section Line, 380 feet from W Section Line
Lease Name: ANTRIM Well #: 1
County: BARBER Total Vertical Depth: 4515 feet

Operator License No.: 6006
Op Name: MOLZ OIL COMPANY
Address: 19159 SW CLAIRMONT
KIOWA, KS 67070

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4514	0	WITH 150 SX CMT
SURF	8.625	273		WITH 200 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 01/10/2008 9:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: PERFORATE 4 1/2" CASING @ 600' & CIRCULATE CMT.
146-74

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/10/2008 11:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SQUEEZED CASING LEAK @ 2440' WITH 200 SX CMT. PIPE COLLAPSED AT 2560', MILLED THROUGH, GOT STUCK JARRED BACK OUT. RESQUEEZED WITH 150 SX CMT. COULDN'T DRILL OUT CMT. GETTING UP METAL. UNABLE TO GET BELOW 2547'. CMT IN PLACE FROM SQUEEZE JOB. PERFORATE 4 1/2" CASING AT 603'. PUMPED DOWN 4 1/2" CASING WITH 200 SX CMT. CMT CIRCULATED BACK TO SURFACE UP 4 1/2" X 8 5/8" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
4430	4445		
4409	4411		


INVOICED
DATE 1-23-08
INV. NO. 200806107

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 17 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

Form CP-2/3

PKT
[Signature]