

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21274-00-00
Spot: NWSESW Sec/Twnshp/Rge: 30-30S-25W
900 feet from S Section Line, 1700 feet from W Section Line
Lease Name: LANG 30C Well #: 1
County: CLARK Total Vertical Depth: 5710 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3540		WITH 2 SX CMT
CIBP		4350		
PROD	5.5	5202	3200	WITH 275 SX CMT 185.58
SURF	8.625	670		WITH 325 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/08/2008 11:20 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: GARY ROWE Company: RITCHIE EXPLORATION Phone: (620) 214-0330

Proposed Plugging Method: CIBP @ 3540' WITH 2 SX CMT. PLUG AT 1550' WITH 15 SX GEL & 50 SX CMT. PLUG AT 700 WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/08/2008 1:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 3540' WITH 2 SX CMT. 1ST PLUG AT 1550' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 700' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4543	4548		
3606	3610		
3601	3603		
3594	3598		

INVOICED
DATE 1-23-08
INV. NO. 2008061114

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 16 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.
Plugged through: CSG

District: 01

RECEIVED
JAN 10 2008
KCC Dodge City

Signed Eric MacLaren
(TECHNICIAN)

Form CP-28
[Handwritten Signature]