

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

ORIGINAL

Form ACO-1
September 1999
Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 33344
Name: Quest Cherokee, LLC **RECEIVED**
Address: P O Box 100
City/State/Zip: Benedict, KS 66714 **JUN 25 2004**
Purchaser: Bluestem Pipeline, LLC **KCC WICHITA**
Operator Contact Person: Doug Lamb
Phone: (620) 698-2250
Contractor: Name: Well Refined Drilling Company, Inc.
License: 33072
Wellsite Geologist: Mark Brecheisen

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:

Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth _____
 Commingled _____ Docket No. _____
 Dual Completion _____ Docket No. _____
 Other (SWD or Enhr.?) _____ Docket No. _____

<u>02/25/04</u>	<u>02/26/04</u>	<u>04/09/04</u>
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 099-23414-0000
County: Labette
_____ -c -se -sw Sec. 7 Twp. 31 S. R. 19 East West
700 feet from S N (circle one) Line of Section
1900 feet from E W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Burris, JoeAnn Well #: 7-1
Field Name: Cherokee Basin CBM

Producing Formation: Not yet complete
Elevation: Ground: 912 Kelly Bushing: _____
Total Depth: 922' Plug Back Total Depth: 918'
Amount of Surface Pipe Set and Cemented at 31.6 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from 918
feet depth to Surface w/ 127 sx cmt.

Drilling Fluid Management Plan WTHM 6-28-07
(Data must be collected from the Reserve Pit)
Chloride content _____ ppm Fluid volume _____ bbls
Dewatering method used _____
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Douglas Lamb
Title: Manager Date: 06/22/04
Subscribed and sworn to before me this 22nd day of June,
2004
Notary Public: Jennifer R. Houston
Date Commission Expires: July 30, 2005

JENNIFER R. HOUSTON
Notary Public - State of Kansas
My Appt. Expires July 30, 2005

KCC Office Use ONLY
 Letter of Confidentiality Received
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

Operator Name: Quest Cherokee, LLC Lease Name: Burris, JoeAnn Well #: 7-1
 Sec. 7 Twp. 31 S. R. 19 East West County: Labette

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i> List All E. Logs Run: Dual Induction Log Compensated Density-Neutron Log	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 70%;">Name</td> <td style="width: 15%;">Top</td> <td style="width: 15%;">Datum</td> </tr> <tr> <td>Lenapah Lime</td> <td>160.5</td> <td>+751.5</td> </tr> <tr> <td>Altamont Lime</td> <td>194</td> <td>+718</td> </tr> <tr> <td>Pawnee Lime</td> <td>323</td> <td>+589</td> </tr> <tr> <td>Oswego Lime</td> <td>396</td> <td>+516</td> </tr> <tr> <td>Verdigris Lime</td> <td>555</td> <td>+359</td> </tr> <tr> <td>Mississippi Lime</td> <td>866</td> <td>+46</td> </tr> </table>	Name	Top	Datum	Lenapah Lime	160.5	+751.5	Altamont Lime	194	+718	Pawnee Lime	323	+589	Oswego Lime	396	+516	Verdigris Lime	555	+359	Mississippi Lime	866	+46
Name	Top	Datum																				
Lenapah Lime	160.5	+751.5																				
Altamont Lime	194	+718																				
Pawnee Lime	323	+589																				
Oswego Lime	396	+516																				
Verdigris Lime	555	+359																				
Mississippi Lime	866	+46																				

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4"	8-5/8"	24.75#	31.6'	"A"	8sx	
Production	6-3/4"	4-1/2"	10.5#	918'	"A"	127sx	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
None	Waiting on pipeline	<div style="border: 2px solid black; padding: 10px; display: inline-block;"> <p style="margin: 0;">RECEIVED</p> <p style="margin: 0;">JUN 25 2004</p> <p style="margin: 0;">KCC WICHITA</p> </div>	

TUBING RECORD		Size	Set At	Packer At	Liner Run
					<input type="checkbox"/> Yes <input type="checkbox"/> No
Date of First, Resumerd Production, SWD or Enhr.			Producing Method		
			<input type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)		
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity

Disposition of Gas	METHOD OF COMPLETION	Production Interval
<input type="checkbox"/> Vented <input type="checkbox"/> Sold <input type="checkbox"/> Used on Lease <i>(If vented, Submit ACO-18.)</i>	<input type="checkbox"/> Open Hole <input type="checkbox"/> Perf. <input type="checkbox"/> Dually Comp. <input type="checkbox"/> Commingled <input type="checkbox"/> Other (Specify) _____	



CONSOLIDATED
OIL WELL
SERVICES
AN INFINITY COMPANY

211 W. 14TH STREET, CHANUTE, KS 66720
620-431-9210 OR 800-467-8676

TICKET NUMBER **24325**

LOCATION CHANUTE

FIELD TICKET

DATE 4-7-04	CUSTOMER ACCT # 6628	WELL NAME BUREAU #7-1	QTR/QTR	SECTION 7	TWP 31S	RGE 19E	COUNTY LB	FORMATION
CHARGE TO QUEST CHEROKEE LLC				OWNER				
MAILING ADDRESS PO BOX 100				OPERATOR				
CITY & STATE BENEDICT, KANSAS 66714				CONTRACTOR				

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION OF SERVICES OR PRODUCT	UNIT PRICE	TOTAL AMOUNT
5401	1-WELL	PUMP CHARGE CEMENT PUMP		525 ⁰⁰
1110	13 SKS	GILSONITE		259 ²⁰
1107	1 SKS	CELLOFLAKE-FLO-SEAL		37 ²⁵
1111B	15 GAL	SODIUM SILICATE		150 ⁰⁰
1215	1 GAL	KCL		22 ⁰⁰
RECEIVED				
JUN 25 2004				
KCC WICHITA				
1123	3360 GAL	CITY WATER (80 BBL)		37 ⁸⁰
5407	32 mi	BLENDING & HANDLING TON-MILES (MINIMUM)		190 ⁰⁰
		STAND BY TIME		
		MILEAGE		
5501	2 HR	WATER TRANSPORTS		160 ⁰⁰
5502	8 HR	VACUUM TRUCKS		600 ⁰⁰
		FRAC SAND		
1126	120 SKS	CEMENT OWC (127 SKS TOTAL)		1356 ⁰⁰
		(OWC; 5# GILSONITE; 1/4# FLO-SEAL)	SALES TAX	120 ⁰⁰
ESTIMATED TOTAL				3450⁸⁶

Ravin 2790

CUSTOMER or AGENTS SIGNATURE _____ CIS FOREMAN Tom H. Till

CUSTOMER or AGENT (PLEASE PRINT) _____ DATE _____

189685

CONSOLIDATED OIL WELL SERVICES, INC.
 211 W. 14TH STREET, CHANUTE, KS 66720
 620-431-9210 OR 800-467-8676

TICKET NUMBER 32882
 LOCATION CHANUTE
 FOREMAN TODD A TINDLE

TREATMENT REPORT

DATE <u>4-7-04</u>	CUSTOMER # <u>6628</u>	WELL NAME <u>JACKS</u> #7-1	FORMATION
SECTION <u>1</u>	TOWNSHIP <u>11E</u>	RANGE <u>11E</u>	COUNTY <u>LB</u>
CUSTOMER <u>QUEST ENERGY LLC.</u>			
MAILING ADDRESS <u>P.O. Box 100</u>			
CITY <u>BENEDICT</u>			
STATE <u>KANSAS</u>		ZIP CODE <u>66714</u>	
TIME ARRIVED ON LOCATION			

TRUCK #	DRIVER	TRUCK #	DRIVER
<u>255</u>	<u>JOHN</u>		
<u>206</u>	<u>WEE</u>		
<u>225</u>	<u>RICHARD</u>		
<u>140</u>	<u>TIM</u>		

TYPE OF TREATMENT

<input type="checkbox"/> SURFACE PIPE	<input type="checkbox"/> ACID BREAKDOWN
<input checked="" type="checkbox"/> PRODUCTION CASING	<input type="checkbox"/> ACID STIMULATION
<input type="checkbox"/> SQUEEZE CEMENT	<input type="checkbox"/> ACID SPOTTING
<input type="checkbox"/> PLUG & ABANDON	<input type="checkbox"/> FRAC
<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> FRAC + NITROGEN
<input type="checkbox"/> MISP. PUMP	<input type="checkbox"/>
<input type="checkbox"/> OTHER	<input type="checkbox"/>

WELL DATA

HOLE SIZE <u>6 7/8</u>	PACKER DEPTH
TOTAL DEPTH <u>922'</u>	PERFORATIONS
	SHOTS/FT
CASING SIZE <u>4 1/2</u>	OPEN HOLE
CASING DEPTH <u>913'</u>	
CASING WEIGHT	TUBING SIZE
CASING CONDITION	TUBING DEPTH
	TUBING WEIGHT
	TUBING CONDITION
TREATMENT VIA	

PRESSURE LIMITATIONS

	THEORETICAL	INSTRUCTED
SURFACE PIPE		
ANNULUS LONG STRING		
TUBING		

INSTRUCTION PRIOR TO JOB CIRCULATE W/ FRESH H₂O, RUN 8 BBL DYE W/ 5 GAL SODIUM SILKATE IN LAST 5 BBL, CEMENT UNTIL DYE RETURN, FLUSH PUMP, PUMP PLUG W/ KEL WATER, SET FLOAT SHOE, CEMENT LEAD IN @ 12.5, TAIL IN @ 13.8

AUTHORIZATION TO PROCEED	TITLE	DATE
--------------------------	-------	------

TIME AM / PM	STAGE	BBL'S PUMPED	INJ RATE	PROPPANT PPG	SAND / STAGE	PSI	
							BREAKDOWN PRESSURE
							DISPLACEMENT
							MIX PRESSURE
							MIN PRESSURE
							ISIP
							15 MIN.
							MAX RATE
							MIN RATE

RECEIVED
JUN 25 2004
KCC WICHITA

TERMS

In consideration of the prices to be charged for our services, equipment and products as set forth in Consolidated Oil Well Services, Inc's (COWS) current Price Schedule, and for the performance of services and supplying of materials; customer agrees to the following terms and conditions.

Terms. Cash in advance unless satisfactory credit is established. On credit sales, invoices payable to P.O. Box 884, Chanute, KS 66720. Invoices payable within 30 days of invoice date. Charges subjected to interest after 30 days from invoice date. Interest will be charged at Maximum rate allowed by law. In the event it is necessary to employ an attorney to enforce collection of such account, customer agrees pay all collection costs and attorney's fees in the amount of 20% of said amount.

Any applicable federal, state or local sales, use, occupation, consumer's or emergency taxes shall be added to the quoted price.

A sales tax reimbursement of 2% is applied to chemical and product charges for all services performed on oil and gas wells in the State of Texas.

All process license fees required to be paid to others will be added to the scheduled prices.

All prices are subject to change without notice.

SERVICE CONDITIONS

Customer warrants that the well is in proper condition to receive the services, equipment, products, and materials to be supplied by COWS.

"The customer shall at all time have complete care, custody, and control of the well, the drilling and production equipment at the well, and the premises about the well. A responsible representative of the customer shall be present to specify depths, pressures, or materials used for any service which is to be performed."

- (a) COWS shall not be responsible for, and customer shall secure COWS against any liability for damage to property of customer and of the well owner (if different from customer), unless caused by the willful misconduct or gross negligence of COWS, this provision applying to but not limited to sub-surface damage and surface damage arising from subsurface damage.
- (b) Customer shall be responsible for and secure COWS against any liability for reservoir loss or damage, or property damage resulting from sub-surface pressure, losing control of the well and/or a well blowout, unless such loss or damage is caused by the willful misconduct of gross negligence of COWS.

- (c) Customer shall be responsible for and secure COWS against any and all liability of whatsoever nature for damages as a result of a subsurface trespass, or an action in the nature thereof, arising from a service operation performed by COWS hereunder.
- (d) Customer shall be responsible for and secure COWS against any liability for injury to or death of persons, other than employees of COWS, or damage to property (including, but not limited to, injury to the well), or any damages whatsoever, irrespective of cause, growing out of or in any way connected with the use of radioactive material in the well hole, unless such damage shall be caused by the willful misconduct or gross negligence of COWS.
- (e) COWS makes no guarantee of the effectiveness of the products, supplies or materials, nor of the results of any treatment or services.
- (f) Because of the uncertainty of variable well conditions and the necessity of relying on facts and supporting services furnished by others, COWS is unable to guarantee the accuracy of any chart interpretation, research analysis, job recommendation or other data furnished by COWS. COWS personnel will use their best efforts in gathering such information and their best judgment in interpreting it, but customer agrees that COWS shall not be responsible for any damage arising from the use of such information except where due to COWS gross negligence or willful misconduct in the preparation or furnishing of it.

WARRANTIES - LIMITATION OF LIABILITY

COWS warrants only title to the products, supplies and materials and that the same are free from defects in workmanship and materials. THERE ARE NO WARRANTIES, EXPRESS OR IMPLIED OR MERCHANTABILITY, FITNESS OR OTHERWISE WHICH EXTEND BEYOND THOSE STATED IN THE IMMEDIATELY PRECEDING SENTENCE. COWS's liability and customer's exclusive remedy in any cause of action (whether in contract, tort, breach of warranty or otherwise) arising out of the sale or use of any products, supplies or materials is expressly limited to the replacement of such products, supplies or materials on their return to COWS or, at COWS's option, to the allowance to the customer of credit for the cost of such items. In no event, shall COWS be liable for special, incidental, indirect, punitive or consequential damages.

COWS personnel will use their best efforts in gathering such information and their best judgement in interpreting it, but Customer agrees that COWS shall not be liable for and CUSTOMER SHALL INDEMNIFY AGAINST ANY DAMAGED ARISING FROM THE USE OF SUCH INFORMATION, even if such is contributed by the COWS negligence or fault.