

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-22194-00-01
Spot: NENWNE Sec/Twnshp/Rge: 6-26S-5E
4910 feet from S Section Line, 1667 feet from E Section Line
Lease Name: MARSH A Well #: 5
County: BUTLER Total Vertical Depth: 2500 feet

Operator License No.: 32693
Op Name: HAWKINS OIL, LLC
Address: 427 S BOSTON AVE STE 915
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2500		
SURF	8.625	200		

81.25

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/09/2007 11:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 222-1252

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE
Date/Time Plugging Completed: 11/09/2007 1:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

11-2-2007, SANDED BACK @ 1940', DUMP BAILED 4 SXS CEMENT ON TOP. 11-5-2007, PARTED CASING @ 1195', LAYED DOWN 29JTS. 4-1/2" CASING. 11-9-2007, RIH W/1" TBG @ 250'. BRADEN PETROLEUM & WELL PLUGGING MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 1300 PM 11-9-2007. BRADEN PETROLEUM & WELL PLUGGING CEMENT TICKET #07-608.

Perfs:

INVOICED
DATE 1-23-08
INV. NO. 2008061096

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 16 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: -096.92259.37.82362 PERFS - 1994'-2004' CIBP @ 2200'.

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

PKT