

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01505-00-00
Spot: E2SWNE Sec/Twnshp/Rge: 33-9S-21W
3300 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: BRAGG Well Number: 3
County: GRAHAM Total Vertical Depth: 3858 feet

Operator License No.: 9449
Op Name: GREAT EASTERN ENERGY & DEV. CO
Address: 550 W. TEXAS STE 660
MIDLAND, TX 79702

Production Casing Size: 5.5 feet: 3853
Surface Casing Size: 8.625 feet: 210

125 39

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/04/2003 10:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: MIKE DAVINGTON Company: GREAT EASTERN ENERGY & DEV. Phone: (785) 623-7520

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls - 18 sxs gel spacer.
No squeeze records. Perforate at 2250' - 1800' - 1050'.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/04/2003 2:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Log Tech hit bridge at 690'.
Ran tubing to cleaned out 2685', PTOH.
Perforated 2250' - 1800' - 1050'.
Ran tubing to 2600'.
Allied pumped 5 sxs gel spacer, followed with 40 sxs 60/40 pozmix - 10% gel with 100# hulls.
Pulled tubing to 1500'.
Allied pumped 100 sxs cement with 400# hulls - cement circulated.
PTOH. Squeezed 80 sxs cement.
Max. P.S.I. 500#. S.I.P. 300#.
Hooked up to backside - pressured 200#. Blew hole in 8 5/8" - hole full.

RECEIVED
SEP 10 2003
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS DEYOUNG #3. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 9-10-03
INV. NO. 2004060490

SEP 05 2003

FRANCIS OIL & GAS

#3

BRAGG

33-9-21W
E2 SW NE

Contr. VEEDER SUPPLY & DEV

GRAHAM

County

E 2308 RB

Comm. 9-22-54

Comp.

11-26-54

IP


3000 BOPD

| Tops | Depth | Datum |
|------|-------|-------|
| Awk | 17.77 | 1 |
| HEEB | 3487 | +1179 |
| TOR | 3504 | -1196 |
| LANS | 3528 | -1220 |
| | | |
| GONG | 3818 | -1510 |
| | | |
| ARB | 3851 | -1543 |
| | | |
| TD | 3858 | -1550 |

Casing
8" 210
5" 3853

DP: DD 3858: SWB 58 BOPH/3
HRS:

COOPER NO POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS