

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03527-00-1E ^{02 KCCopB}
Spot: E2SWNE Sec/Twnshp/Rge: 26-11S-19W
3300 feet from S Section Line, 1650 feet from E Section Line
Lease Name: VINE SOOK Well #: 5
County: ELLIS Total Vertical Depth: 620 feet

Operator License No.: 3194
Op Name: TRI UNITED, INC
Address: 950 270TH AVE
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3630	0	w/650 sxs cmt
SURF	8.625	160	0	w/100 sxs cmt

\$35.00

Well Type: SWD DH UIC Docket No: _____ Date/Time to Plug: 09/06/2007 11:30 AM
Plug Co. License No.: 3194 Plug Co. Name: TRI UNITED, INC
Proposal Rcvd. from: EUGENE LEIKER Company: TRI UNITED, INC Phone: (785) 628-3670

Proposed Plugging Method: Ordered 100 sxs 60/40 pozmix - 4% gel.
Note: Original Docket D-04,546 was cancelled.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/06/2007 12:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Tried to wash well down - got to 620'.
Got out of hole - squeezed 0' - 200' w/100 sxs - pumped into annulus 8 5/8" w/10 sxs by operator.
RIH with tubing to 620'. Allied rigged to tubing and pumped 70 sxs 60/40 pozmix - 4% gel to circulate cement to surface.
Pulled tubing - topped off casing w/10 sxs 60/40 pozmix - 4% gel - hole standing full.
Rigged to 8 5/8" - pressured to Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 10 2007
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 9-20-07
INV. NO. 2008060437

Remarks: ALLIED CEMENTING COMPANY-TICKET #33159.

Plugged through: TBG

District: 04

Handwritten initials

Signed _____

Signature of Technician
(TECHNICIAN)

Handwritten initials