

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24804-00-00  
Spot: SENE SW Sec/Twnshp/Rge: 1-17S-15W  
1650 feet from S Section Line, 2310 feet from W Section Line  
Lease Name: HEJNY A Well #: 4  
County: BARTON Total Vertical Depth: 3455 feet

Operator License No.: 4656  
Op Name: DAVIS PETROLEUM, INC.  
Address: 7 SW 26 AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3455	2687	150 SX
SURF	8.625	963	0	400 SX
T1	2.875	3452		

112.29

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/20/2007 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: L.D. DAVIS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: Ordered 280 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/20/2007 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Pulled casing to 1675'.  
Tied onto casing - pumped 165 sxs cement with 300# hulls.  
Pulled to 1000' - pumped 40 sxs cement with 100# hulls.  
Pulled to 550' - pumped 40 sxs cement.  
Pulled to 100' - pumped 150 sxs cement - circulated to surface.

Perfs:

Top	Bot	Thru	Comments
3404	3408		
3384	3388		
3368	3372		

INVOICED

DATE 1-2-08  
INV. NO. 2008060996

RECEIVED  
KANSAS CORPORATION COMMISSION

DEC 26 2007

CONSERVATION DIVISION  
WICHITA, KS

Remarks: COPELAND CEMENTING COMPANY-TICKET #C33405. 38.59895 - 98.93340.

Plugged through: CSG

District: 04

PD

Signed

Bruce Rodie

(TECHNICIAN)

PR

DAVIS PETROLEUM  
GREAT BEND KS 67530

1-17S-15W  
SE NE SW


site: 5-1/4 N OF OLMITZ KS  
contr: PETROMARK DRILLING #1  
geol: KIM B. SHOEMAKER

#4 HEJNY A

cy: BARTON  
field: LEOVILLE

AP 15-009-24804

fr date 09/14/2004 spd date 11/08/2004 drig comp 11/16/2004 card issued 02/07/2005 last revised 02/07/2005



ELV: 1967 KB, 1961 GL LOG

tops	depth/datum
ANH	969 +998
TOP	2908 -941
HEEB	3143 -1176
BR LM	3206 -1239
LANS	3222 -1255
BKC	3428 -1461
PBTD	3430 -1463
ARB	3455 -1488
RTD	3455 -1488

IP status:  
OIL, P 8 BO & 12 BWPD, LKC 3368-3408 OA, 12/14/2004  
CSG: 8-5/8" 962.89 / 400 SX (ALT 2), 5-1/2" 3455 / 150 SX  
COMMENT: MI & RURT 11/7/2004  
NO CORES  
DSTS TAKEN - DETAILS NA  
TRGT ZN: ARB (OIL), PTD 3500 (ARB), MICT: CO, PB.3430,  
PF (LKC) 3368-3372, 3384-3388, 3404-3408, W / 2 SFF, AC 4000  
GAL (15%), SWB LD, SO, SET 2-7/8" TBG AT 3452, NO PKR,  
POP, IFF 8 BO & 12 BWPD, DOFP 12/14/2004 - NO OTHER  
INFO AVAILABLE - TEMP COMP 2/7/2005

COPYRIGHT 2004  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS