

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04173-00-00
Spot: SWNESW Sec/Twnshp/Rge: 1-17S-15W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: HEJNY A Well #: 2
County: BARTON Total Vertical Depth: 3476 feet

Operator License No.: 4656
Op Name: DAVIS PETROLEUM, INC.
Address: 7 SW 26 AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3472	0	w/225 sxs cmt
SURF	8.625	985	0	w/150 sxs cmt

112.97

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/20/2007 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 14 sxs gel - 500# hulls.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/20/2007 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Tied onto casing - pumped 50 sxs cement with 100# hulls.
Pumped 14 sxs gel with 150# hulls.
Pumped 220 sxs cement. Shut down one hour - more water.
Pumped 10 sxs cement in backside.
Max. P.S.I. 500#.
Pumped 40 sxs cement.
Max. P.S.I. 500#. S.I.P. 300#.

Perfs:

INVOICED
DATE 1-2-08
INV. NO. 2008060996

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 26 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND CEMENT COMPANY-TICKET #33406. 38.59893 - 98.93532.

Plugged through: CSG

District: 04

NO

Signed Bruce Rodie
(TECHNICIAN)

DEC 21 2007

pat

COOP REFG ASSN #2 HEJNY 'A' 1-17-15W
 Contr. COOP REFG ASSN SW NE SW
 E. 1978RB Comm. Comp. 5-17-57 IP 51 BOPD/ARB
 BARTON County

Tops	Depth	Datum
Arh	976	+ 1002
TOP	2923	-945
HEEB	3154	-1176
TOR	3170	-1192
LANS	3218	-1240
B/KC	3443	-1465
ARB	3471	-1493
TD	3476	-1498

Casing
 8" 985
 5" 3472
 DST 3286-3310/1 HR, 300' G,
 200' O & GCM, BHP 710#
 DST 3362-90/1 HR, 28' WTRY MUD
 BHP 610#
 DST 3472-76/1 HR, 270' G,
 1357' O, BHP 950#
 1200' FIH/1 HR; BAIL 4 1/2 BO &
 LEOVILLE POOL 1 1/2 B SW: PMP
 66 BO & 4 BW/
 14 HRS

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS