

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21577-00-00
Spot: W2NENWSE Sec/Twnshp/Rge: 9-16S-13W
2310 feet from S Section Line, 1760 feet from E Section Line
Lease Name: MAES Well #: 1
County: BARTON Total Vertical Depth: 3380 feet

Operator License No.: 31561
Op Name: HOFFMAN, CHRIS DBA C & K OIL COM
Address: 410 B ST PO BOX 531
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3378	0	w/unknown sxs cmt
SURF	8.625	309	0	w/unknown sxs cmt 109.85

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/12/2007 8:00 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: CHRIS HOFFMAN Company: C&K OIL COMPANY Phone: (620) 587-0150

Proposed
Plugging
Method:

Order 280 sxs 60/40 pozmix - 4% gel - 800#-1000# hulls - 15 sxs gel spacer.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 11/12/2007 12:00 AM KCC Agent: HERB DEINES

Actual Plugging Report:

Ran tubing to 3300' - pumped 25 sxs cement with 100# hulls.
Pulled tubing to 3065' - pumped 15 sxs gel with 150# hulls.
Pulled tubing to 1600' - pumped 230 sxs cement with 700# hulls with cement to surface.
Pulled tubing.
Tied onto annulus and pumped 35 sxs cement.
Max. P.S.I. 400#.
Tied onto production casing and pumped 40 sxs cement.

Perfs:


INVOICED
DATE 1-2-08
INV. NO. 2008060995

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 26 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed  (TECHNICIAN)

Form CP-2/3

DEC 20 2007

AMBER OIL COMPANY
 1022 UNITED FOUNDERS TWR.
 OKLAHOMA CITY, OK 73112
 CONTR ALLEN DRILLING CO

#1 MAES 110'W, NE NW SE 9-16-13W

CTY BARTON

GEOLOGICAL FIELD TRAPP

E 1916 KB CM 9/20/79 CARD ISSUED 11/3/79 IP P 20 BOPD

API 15-009-21,577 ARB OH 3378-80

	+	+
	+	+

NOTE: WAS ABD LOC

SMP	TOPS	DEPTH	DATUM
ANH		868	+1048
BANH		899	+1017
BR LM		3125	-1209
LANS		3135	-1219
ARB		3376	-1460
RTD		3380	-1464

8-5/8" 309
 5-1/2" 3378

DST (1) 3368-80/30-30-30-30, REC
 660' GCMO, 1440'M, NW, PKR FAILED
 AFTER 5"
 NO PRESSURES RECORDED

MICT - CO, (ARB OH), NAT, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS