

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-19184-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 22-14S-16W  
2310 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: DREILING B Well #: 2  
County: ELLIS Total Vertical Depth: 3401 feet

Operator License No.: 4787  
Op Name: TDI, INC.  
Address: 1310 BISON RD  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3399	0	w/100 sxs cmt
SURF	8.625	722	0	w/350 sxs cmt

110.53

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/06/2007 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: TERRY PIESKER Company: TDI, INC. Phone: (785) 628-2593

Proposed  
Plugging  
Method:

Ordered 280 sxs 60/40 pozmix - 4% gel - 800# hulls - 19 sxs gel.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/06/2007 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto 5 1/2" - pumped 100 sxs cement with 400# hulls.  
Pumped 19 sxs gel with 200# hulls.  
Pumped 120 sxs cement - went on vacuum - stopped - let set one hour.  
Tied on the 8 5/8" - pumped 5 sxs cement to Max. P.S.I. 200#.  
Back down the 5 1/2" - pumped 55 sxs cement with 200# hulls.  
Tube full.

Perfs:

**INVOICED**  
DATE 12-19-07  
INV. NO. 2008060949


**RECEIVED**  
**DEC 10 2007**  
**KCC WICHITA**

Remarks: ALLIED CEMENTING COMPANY-TICKET #30540.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)


*Handwritten initials*

34

M. B. ARMER #2 DREILING B 22-14-16W  
 NW NW SW  
 Contr. \_\_\_\_\_ ELLIS County  
 E. 1876 Comm. \_\_\_\_\_ Comp. 7-14-50 IP 100 BOPD & 8% WTR

Tops	Depth	Datum
ANH	965	+ 911
HEEB	3063	- 1187
TOR	3082	- 1206
LANS	3110	- 1234
CONG	3360	- 1484
ARB	3399	- 1523
T.D.	3404	- 1528

Casing \*  
 8" 720 DP 3404: 7 GOPH  
 5" 3399 ACID 500  
 SWB 6 BOPH/3 HRS:



INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS