

9-21

To: 6 031168  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,323 -00-0  
60' SE N SE NW, SEC. 33, T. 6 S, R. 21 W/E

3030 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5266

Lease Name Johnson Well # B 1

Operator: K and E Drilling Inc.

County Graham 126.78

Name & Address 100 S. Main Suite 300

Well Total Depth 3901 feet

Wichita, Ks. 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ U&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cement Co. License Number \_\_\_\_\_

Address Russell, Ks.

Company to plug at: Hour: \_\_\_\_\_ PM Day: 21 Month: Sept Year: 19 88

Plugging proposal received from Al Hammersmith

(company name) K and E (phone) \_\_\_\_\_

were: 8 5/8" set at 258' w/185 sks cwc. 5 1/2" set at 3831' w/175 sks. Port

collar set at 1836' w/500 sks. Perf 3480' - 83' w/disposal in O.H. Below permanent packer at 3820

Dusal completion. Order 450 sks 60/40 Poz 8% Gel 2% Ca C 500# Hulls. Allied Cement Co. OWS Water

Trucks.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 21 1988  
100-1-88  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Conservation Division Hour: 12:20PM Day: 21 Month: Sept Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 5 1/2" casing w/375 sks Cement Blend w/500# Hulls

mixed into max psi. Lock up of 1000#. Released pressure back to 300# psi. Closed in.

Plug complete. Cement was in 2" bull plug and gate in casing. Head backside full of cement  
at surface.

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-25-88

INV. NO. 22693

Signed Carl Goodrow  
Carl Goodrow (TECHNICIAN)