

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01579-00-00  
Spot: SESWNW Sec/Twnshp/Rge: 30-9S-18W  
2970 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: HILGERS B Well #: 1  
County: ROOKS Total Vertical Depth: 3615 feet

Operator License No.: 31070  
Op Name: EAGLE RIVER ENERGY CORPORATIO  
Address: 7060 S YALE # 702  
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3612	0	w/unknown sxs cmt
SURF	8.625	260	0	w/unknown sxs cmt <u>117.49</u>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/07/2007 9:30 AM  
Plug Co. License No.: 4072 Plug Co. Name: PLAINS, INC  
Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (620) 793-3645

Proposed Plugging Method: Ordered 650 sxs 60/40 pozmix - 4% gel - 1300# hulls.  
Emergency plug with rig over the hole.  
Operator elected all cement plug.  
1995 squeeze at 1049' w/140 sxs.  
Junk in the hole - 47 joints - 118 rods and pump.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/07/2007 2:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

RIH with tubing to 1519'. Rigged to tubing - pumped 100 sxs 60/40 pozmix - 4% gel followed with 100 sxs 60/40 pozmix with 300# hulls mixed in.  
Pulled tubing to 800'. Rigged to tubing with a swedge - pumped 320 sxs 60/40 pozmix with 1000# hulls mixed in - circulated cement out of 5 1/2" casing.  
Pulled tubing - topped off 5 1/2" casing with 35 sxs cement.  
Hole standing full.  
Pumped 50 sxs in 8 5/8". Max. P.S.I. 300#. S.I.P. 300#.

INVOICED  
DATE 12/19/07  
INV. NO. 2008060926

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 12 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

100

Signed *Pat Staab*  
(TECHNICIAN)

Form CP-2/3

DEC 10 2007

GRANT OIL COMPANY #1 HILGERS 'B' 30-9-18W  
 SE SW NW  
 Contr. BIRMINGHAM-BARTLETT ROOKS County  
 E 2197 Comm. 12-10-57 Comp. 2-28-58 IP 81 BOPD

Tops	Depth	Datum	Casing
ANH	1560	+637	8" 260
			5" 3612
TOP	3119	-922	
HEEB	3327	-1130	DST 3263-82/1 HR, 80' MUD, BHP 1217#
TOR	3349	-1152	
KC	3368	-1171	DST 3293-3305/1 HR, 30' MUD, BHP 1100#
			ACID 250: SWB 1 BOPH, NW
ARB	3611	-1414	BAUMGARTEN POOL
TD	3615	-1418	

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

