

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03432-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 26-10S-20W
990 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: SUTOR C Well Number: 1
County: ROOKS Total Vertical Depth: 3777 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY
Address: 805 CODELL RD.
CODELL, KS 67663

Production Casing Size: 5.5 feet: 3768 150 SX CMT
Surface Casing Size: 8.625 feet: 240 150 SX CMT

122 75

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/09/2003 8:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DON BOWMAN Company: BOWMAN OIL COMPANY Phone: (785) 434-2286

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 10% gel - 20 sxs gel - 500# hulls.
Perf casing at 900' and 1700'.
WLM 3770'.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/09/2003 9:00 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.U. Cementers - squeezed 25 sxs cement with 300# hulls, followed with 20 sxs gel and 150 sxs cement with 100# hulls.
Max. P.S.I. 1000#. S.I.P. 300#.
8 5/8" S.P. - squeezed with 25 sxs cement with 100# hulls.
Max. P.S.I. 500#. S.I.P. 400#.

RECEIVED
10-30-2003
OCT 30 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Dennis L. Hamel
(TECHNICIAN)

OCT 23 2003

100.
INVOICED
DATE 10-30-03
INVOICE NO. 2004060694

EL DORADO REFINING COMPANY #1

SUTOR

26-10-20W
NW SW SE

Contr. SIERRA PETROLEUM

ROOKS

County

E 2217RB Comm.

Comp. 11-1-57

IP 2 1/4 BOPD/ARB

PHY POT

Tops	Depth	Datum
HEEB	3437	-1220
TOR	3465	-1248
LANS	3476	-1259
CONG	3718	-1501
SIMP	3752	-1535
ARB	3766	-1549
TD	3777	-1560

Casing

8" 240

5" 3768

DST 3500-25/1 HR, 250' MDY WTR
BHP 1080#

DST 3530-60/1 HR, 65' OCM, BHP
1080#

DST 3766-73/1 HR, 25' OCM, BHP
1090#

MARGOTTE POOL

CO 3773: SWB 4
BOPH/3 HR: DD
3777: SWB 15
BOPH

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS