

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20569-00-00

Spot: NESE

Sec/Twnshp/Rge: 34-4S-42W

1820 feet from S Section Line,

600 feet from E Section Line

Lease Name: OBRIEN

Well #: 1-34

County: CHEYENNE

Total Vertical Depth: 1389 feet

Operator License No.: 30282

Op Name: LOBO PRODUCTION, INC

Address: 6715 RD 22
GOODLAND, KS 67735

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1381	0	55 SX CMT
SURF	7	136	0	33 SX CMT

45.14

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 11/20/2007 10:30 AM

Plug Co. License No.: 30282

Plug Co. Name: LOBO PRODUCTION, INC

Proposal Rcvd. from: RICHARD MILLER

Company: LOBO PRODUCTION, INC

Phone: (785) 899-5684

Proposed Plugging Method: Ordered 150 sxs common cement.
Plug through casing.

Plugging Proposal Received By: HERB DEINES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/20/2007 11:00 AM

KCC Agent: DARREL DIPMAN

Actual Plugging Report:

7" surface casing set at 136' w/33 sxs cement.
4 1/2" production casing set at 1381' w/55 sxs cement.
TD 1389'. PBTD 1351'.
Connected to 4 1/2" production casing - pumped 100 sxs cement.
Connected to 7" surface casing - pumped 20 sxs cement.

Perfs:

Top	Bot	Thru	Comments
1322	1332		
1292	1312		

INVOICED
DATE 12-17-07
INV. NO. 2008060908

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 03 2007

Remarks: SAINT FRANCIS SAND-TICKET#13606.

Plugged through: CSG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

Form CP-2/3

NOV 22 2007

LOBO PRODUCTION
GOODLAND KS 67735

34-04S-42W
1820' FSL & 600' FEL, SEC

#1-34 O'BRIEN

site: 7-1/4 S & 10-3/4 W OF ST FRANCIS KS city: CHEYENNE API 15-023-20569
cont: POE SERVICING field: CHERRY CREEK NIOBRARA
geol: GAS AREA
fr spd drig card last
date 06/04/2004 date 06/20/2004 comp 06/22/2004 issued 08/30/2004 revised 08/30/2004

ELV: 3512 GL LOG	
tops.....	depth/datum
NIOB.....	1292 +2220
PBTD.....	1351 +2161
RTD.....	1389 +2123

IP status:
D&A, NIOB, 07/05/2004
CSG: 7" 136 / 33 SX (ALT 1), 4-1/2" 1381 / 55 SX
COMMENT: SURF CSG SET AHEAD 6/8/2004 W/WOOFER
PUMP & WELL RIG; WELL DRILD W/CABLE TOOLS & AIR
COMPRESSOR
NO CORES OR DSTS
TRGT ZN: NIOB (GAS), PTD 1400 (NIOB), MICT - CO, PB
1351, PF (NIOB) 1292-1312, 1322-1332, W / 2 SPF, SWB DWN,
NON-COMMERCIAL, SI - EVAL, DECISION MADE TO P & A
7/5/2004

COPYRIGHT 2004
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS