

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01507-00-06
Spot: E2NWNE Sec/Twnshp/Rge: 33-9S-21W
4620 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: BRAGG Well Number: 6
County: GRAHAM Total Vertical Depth: 3879 feet

Operator License No.: 9449
Op Name: GREAT EASTERN ENERGY & DEV. CO
Address: 550 W. TEXAS STE 660
MIDLAND, TX 79702

Production Casing Size: 5.5 feet: 3872
Surface Casing Size: 8.625 feet: 195

#126 07

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/03/2003 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: MIKE DAVINGTON Company: GREAT EASTERN ENERGY & DEV. Phone: (785) 623-7520

Proposed Plugging Method: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
Fluid level 1500'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 09/03/2003 2:00 PM KCC Agent: HERB DEINES

Actual Plugging Report:

8 5/8" to 195'. 5 1/2" to 3872'. 4 1/2" liner to unknown. Fluid level 1500'+.
Tied onto annulus and pressured to 800#.
Tied onto 4 1/2" x 5 1/2" annulus and pressure to 800#.
Tied onto 4 1/2" casing - pumped 200 sxs cement with 500# hulls.
Max. P.S.I. 700#. S.I.P. 300#.

RECEIVED
SEP 10 2003
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS DEYOUNG #2. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed


(TECHNICIAN)

INVOICED

DATE 9.10.03
INV. NO. 2004060490

Form CP-2/3

SEP 05 2003

33-9-21W
E2 NW NE

FRANCIS OIL & GAS ETAL #6 BRAGG


Contr. M B ARMER County GRAHAM

E 2315 R60mm Comp 2-1-55 IP 240 BOPD
PHY POT

Tops	Depth	Datum	Casing
APh	1784		8" 1.95
TOR	3515	-1200	5" 3872
LANS	3540	-1225	
CONG	3830	-1515	
ARB	3872	-1557	
ID	3879	-1564	

CO 3879: 11 BOPH, NATL

COOPER NORTH POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS