

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20367-00-02
Spot: SENESE Sec/Twnshp/Rge: 18-31S-6E
1392 feet from S Section Line, 619 feet from E Section Line
Lease Name: WEIGLE Well #: 4
County: COWLEY Total Vertical Depth: 2965 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2965		80 SX CMT
SURF	8.625	207		100 SX CMT

96.36

Well Type: EOR UIC Docket No: _____ Date/Time to Plug: 11/29/2007 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 11/29/2007 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2800', DUMP BAILED 4 SXS CEMENT ON TOP. NO PIPE RECOVERY. RIH W/TBG @ 350', COPEAND ACID SERVICE MIXED & PUMPED 55 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. P & A COMPLETE. PLUG DOWN 1200PM 11-29-2007. COPELAND CEMENT TICKET #32263. CEMENT WAS TO SURFACE ON BACKSIDE OF 4-1/2" CSG. DOCKET #E-23,269

Perfs:

Top	Bot	Thru	Comments
2910	2914		
2890	2892		
2884	2885		

INVOICED
DATE 1-30-08
INV. NO. 2008061127

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 24 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: -096.80865,37.34896, PBTD 2965', PERF 2884'-92', 2910'-14'

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

PKA