

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20643-00-01
Spot: SESWNE Sec/Twnshp/Rge: 18-31S-6E
2742 feet from S Section Line, 1721 feet from E Section Line
Lease Name: WEIGLE Well #: 6
County: COWLEY Total Vertical Depth: 2979 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2978		125 SX CMT
SURF	8.625	197		110 SX CMT <i>96-82</i>

Well Type: EOR UIC Docket No: E25231.1 Date/Time to Plug: 12/03/2007 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 12/03/2007 3:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @2410', DUMP BAILED 4 SXS CEMENT ON TOP. NO PIPE RECOVERY, RIH W/TBG @ 450', COPLAND ACID SERVICE MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. P&A COMPLETE. PLUG DOWN 1500 PM 12-3-2007. COPELAND CEMENT TICKET #32272. CEMENT WAS TO SURFACE ON BACKSIDE OF 4-1/2" CASING. DOCKET #E-25,231.

Perfs:

Top	Bot	Thru	Comments
2474	2518		

INVOICED
DATE 1-30-08
INV. NO. 2008061127

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 24 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: -096.81246,37.35251, PBTD 2700', PERFS 2474'-2518'

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)