

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-21047-00-01
Spot: SWSENW Sec/Twnshp/Rge: 18-31S-6E
2651 feet from S Section Line, 3340 feet from E Section Line
Lease Name: WEIGLE Well #: 9
County: COWLEY Total Vertical Depth: 2956 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|------------------------|
| PROD | 5.5 | 2942 | | |
| SURF | 8.625 | 205 | | 90 SX CMT <u>96.07</u> |

Well Type: EOR UIC Docket No: E25231.2 Date/Time to Plug: 11/29/2007 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 11/29/2007 3:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2400', DUMP BAILED 4 SXS CEMENT ON TOP. CASING LOOSE @ 280', LAYED DOWN 5-1/2" CASING. RIH W/TBG @ 350', COPELAND ACID SERVICE MIXED & PUMPED 110 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. P & A COMPLETE. PLUG DOWN 1500 PM 11-29-2007. COPELAND CEMENT TICKET #32264. DOCKET #E-25,231.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2942 | 2956 | | |
| 2464 | 2510 | | |
| 2154 | 2224 | | |

INVOICED
DATE 1-30-08
INV. NO. 2008061127

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 24 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: -096.81801,37.35242, PBTB 2910', PERFS 2464'-2510'

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)

PKS