

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22050-00-00
Spot: NESESE Sec/Twnshp/Rge: 8-16S-28W
900 feet from S Section Line, 330 feet from E Section Line
Lease Name: JOE BOB JAMES TRUST Well #: 8-1
County: LANE Total Vertical Depth: 4560 feet

Operator License No.: 32639
Op Name: CORAL PRODUCTION CORPORATION
Address: 1600 STOUT ST STE 1500
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4313	2450	WITH 125 SX CMT
SURF	8.625	255		

148.20

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/21/2008 10:45 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JIM WEBER Company: CORAL PRODUCTION Phone: _____

Proposed Plugging Method: SAND BACK TO 4020' WITH 5 SX CMT. PLUG AT 2120' WITH 50 SX CMT. PLUG AT 1320' WITH 80 SX CMT. PLUG AT 780' WITH 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN
Date/Time Plugging Completed: 01/21/2008 1:05 PM

Witness Type: COMPLETE (100%)
KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SAND BACK TO 4020' WITH 5 SX CMT. 1ST PLUG AT 2120' WITH 50 SX CMT. 2ND PLUG AT 1320' WITH 80 SX CMT. 3RD PLUG AT 780' WITH 50 SX CMT. 4TH PLUG AT 280' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4262	4266	OH	
4086	4092	OH	

INVOICED


DATE 1-30-08
INV. NO. 200806128

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 28 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01



Signed Eric MacLaren
(TECHNICIAN)

Form CP-2/3 *POST*