

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19282-00-00
Spot: SENENE Sec/Twnshp/Rge: 29-30S-7E
4231 feet from S Section Line, 490 feet from E Section Line
Lease Name: STOLP Well #: 5
County: COWLEY Total Vertical Depth: 2895 feet

Operator License No.: 9576
Op Name: WHITEMAN, RON DBA GEN-DOR OIL C
Address: 8135 281ST RD
CAMBRIDGE, KS 67023

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2868		35 SX
SURF	8.625	47		45 SX

94.09

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/19/2007 8:00 AM
Plug Co. License No.: 9576 Plug Co. Name: WHITEMAN, RON DBA GEN-DOR OIL CO.
Proposal Rcvd. from: RONNIE WHITEMAN Company: GEN-DOR OIL COMPANY Phone: (620) 467-2615

Proposed Plugging Method: FILL BOTTOM OF HOLE W/SAND TO 50' ABOVE PERFS DUMP BAIL 6 SXS CEMENT ON TOP. PULL PIPE, CIRCULATE CEMENT FROM 350'. RIH W/TBG TAG BOTTOM PLUG. PRODUCTION CASING HAS ALREADY BEEN PULLED.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/21/2007 10:30 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

12-19-2007, CIRCULATED HOLE CLEAN @ 878', SHUT DOWN, REPAIRS. 12-20-2008, RIH W/TBG TO TAG BOTTOM PLUG, TBG STACKED OUT @ 1207', TAGGED SOLID, COULD NOT GET BACK INTO CUT CSG. W/TBG @ 1190', GEN-DOR MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL, FLUIDS CIRCULATED @ SURFACE DURING CEMENT JOB. PULLED TBG @ 350', GEN-DOR OIL CO. MIXED & PUMPED 140 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 1500 PM 12-20-2007. UNITED CEMENTING TICKET #8168. 1207' OF 5-1/2" CSG WAS PULLED FROM THIS WELL.

Perfs:

Top	Bot	Thru	Comments
2868	2895		
2314	2320		
2255	2261		

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 28 2008

CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 1-30-08
INV. NO. 2008061/29

Remarks: -096.67791.37.41485, PERFS 2255'-2261, 2314'-20'

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

PK