

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-22292-00-00
Spot: SWNENE Sec/Twnshp/Rge: 29-30S-7E
4181 feet from S Section Line, 1162 feet from E Section Line
Lease Name: MELVIN STOLP Well #: 9
County: COWLEY Total Vertical Depth: 2905 feet

Operator License No.: 9576
Op Name: WHITEMAN, RON DBA GEN-DOR OIL C
Address: 8135 281ST RD
CAMBRIDGE, KS 67023

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2903		50 SX CMT
SURF	8.625	214		85 SX CMT. <u>94.41</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/14/2007 8:00 AM
Plug Co. License No.: 9576 Plug Co. Name: WHITEMAN, RON DBA GEN-DOR OIL CO.
Proposal Rcvd. from: RONNIE WHITEMAN Company: GEN-DOR OIL COMPANY Phone: (620) 467-2615

Proposed Plugging Method: FILL BOTTOM TOP OF HOLE W/SAND TO 50' ABOVE PERFS DUMP BAIL 6 SXS CEMENT ON TOP. PULL PIPE, CIRCUALTE CEMENT FROM 350'. RIH W/TBG TAG BOTTOM PLUG. PRODUCTION CASING HAS ALREADY BEEN PULLED.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/14/2007 2:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

12-14-2007, RIHW/TBG TO TAG BOTTOM PLUG, TBG STACKED OUT @ 1157', TAGGED SOLID, COULD NOT GET BACK INTO TO CUT CSG. W/TBG @ 1145', GEN-DOR MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL, FLUIDS CIRCULATED @ SURFACE DURING CEMENT JOB. PULLED TBG @ 350', GEN-DOR OIL CO. MIXED & PUMPED 140 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 1430 PM 12-14-2007. UNITED CEMENTING TICKET #8074. 1157' OF 4-1/2" CSG WAS PULLED FROM THIS WELL.

Perfs:

Top	Bot	Thru	Comments
2882	2892		
2870	2878		

INVOICED
DATE 1-30-08
INV. NO. 200806129

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 28 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: -096.68022,37.41471, PERFS 2870'-2892'

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

PKT